

U.S. 101 MP 98.47 Unnamed Tributary to West Fork Hoquiam River (WDFW ID 993702): Preliminary Hydraulic Design Report



**Paul DeVries Ph.D., PE, CFP, FPT20-11347
Stream Design Engineer, Fisheries Biologist, Fluvial Geomorphologist
Kleinschmidt Associates**

**Ben Cary PE, FPT20-14284
Stream Design Engineer
Kleinschmidt Associates**

**Andrew Nelson LG, FPT20-36866
Fluvial Geomorphologist
Northwest Hydraulic Consultants**

**Isha Deo EIT, FPT20-32443
Stream Design Engineer
Kleinschmidt Associates**

**Darrell Sofield LG
Fluvial Geomorphologist
Northwest Hydraulic Consultants**

Americans with Disabilities Act (ADA) Information

Materials can be made available in an alternative format by emailing the WSDOT Diversity/ADA Affairs Team at wsdotada@wsdot.wa.gov or by calling toll free: 855-362-4ADA (4232). Persons who are deaf or hard of hearing may contact that number via the Washington Relay Service at 7-1-1.

Title VI Notice to Public

It is Washington State Department of Transportation (WSDOT) policy to ensure no person shall, on the grounds of race, color, national origin, or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For Title VI complaint forms and advice, please contact OEO's Title VI Coordinator at 360-705-7082 or 509-324-6018.

Contents

1	Introduction	1
2	Watershed and Site Assessment.....	3
2.1	Watershed and Land Cover	3
2.2	Geology and Soils	5
2.3	Floodplains	5
2.4	Site Description	5
2.5	Fish Presence in the Project Area.....	8
2.6	Wildlife Connectivity	9
2.7	Site Assessment.....	9
2.7.1	Data Collection.....	9
2.7.2	Existing Conditions.....	10
2.7.3	Fish Habitat Character and Quality.....	13
2.8	Geomorphology	14
2.8.1	Reference Reach Selection	14
2.8.2	Channel Geometry.....	14
2.8.3	Sediment.....	17
2.8.4	Vertical Channel Stability.....	17
2.8.5	Channel Migration	20
2.8.6	Riparian Conditions, Large Wood, and Other Habitat Features.....	20
3	Hydrology and Peak Flow Estimates	22
4	Hydraulic Analysis and Design	25
4.1	Model Development	25
4.1.1	Topographic and Bathymetric Data.....	25
4.1.2	Model Extent and Computational Mesh	25
4.1.3	Materials/Roughness.....	28
4.1.4	Boundary Conditions	30
4.1.5	Model Run Controls.....	34
4.1.6	Model Assumptions and Limitations	34
4.2	Existing-Conditions Model Results.....	36
4.3	Natural-Conditions Model Results	42

4.4	Proposed Channel Design	48
4.4.1	Floodplain Utilization Ratio	48
4.4.2	Channel Planform and Shape	48
4.4.3	Channel Alignment	51
4.4.4	Channel Gradient	52
4.5	Design Methodology	52
4.6	Future Conditions: Proposed 13-Foot Minimum Hydraulic Opening	52
4.7	Water Crossing Design	60
4.7.1	Structure Type	60
4.7.2	Minimum Hydraulic Opening Width and Length.....	60
4.7.3	Freeboard	61
5	Streambed Design	63
5.1	Bed Material.....	63
5.2	Channel Complexity	64
5.2.1	Design Concept	64
6	Floodplain Changes	67
6.1	Floodplain Storage	67
6.2	Water Surface Elevations	67
7	Climate Resilience	70
7.1	Climate Resilience Tools.....	70
7.2	Hydrology	70
7.3	Climate Resilience Summary	71
8	Scour Analysis	72
8.1	Lateral Migration.....	72
8.2	Long-term Aggradation/Degradation of the Riverbed.....	72
8.3	Local Scour	72

Figures

Figure 1: Vicinity map	2
Figure 2: Land cover map (NLCD 2016). Approximate catchment area upstream of the culvert is depicted	4
Figure 3: Geologic map. Approximate catchment area upstream of the culvert is depicted	6
Figure 4: Soils map. Approximate catchment area upstream of the culvert is depicted	7
Figure 5: Culvert inlet (left) and outlet (right)	10
Figure 6: West Fork Hoquiam River	11
Figure 7: Rootwad log in project stream.....	11
Figure 8: Natural log weir.....	12
Figure 9: Examples of embedded and channel spanning logs upstream of the culvert.....	12
Figure 10: Example of a vertical bank with vegetation.....	12
Figure 11: Reference reach and locations of BFW measurements and substrate sampling.....	15
Figure 12: Cross-section profiles surveyed in 2021 for BFW determination	16
Figure 13: WSDOT's surveyed cross-section profiles upstream of the culvert.....	16
Figure 14: Watershed-scale longitudinal profile and gradients of the Middle Fork Hoquiam River and project stream; plot includes comparison of LiDAR with WSDOT survey data; dashed red line is upstream grade extended downstream.....	18
Figure 15: Ratio of gage-based flood peak magnitudes vs. regression-based estimates, plotted against drainage area	24
Figure 16: Existing-conditions computational mesh with underlying terrain	26
Figure 17: Natural-conditions computational mesh with underlying terrain.....	27
Figure 18: Proposed-conditions computational mesh with underlying terrain	27
Figure 19: Spatial distribution of roughness values in SRH-2D existing-conditions model	28
Figure 20: Spatial distribution of roughness values in SRH-2D natural-conditions model	29
Figure 21: Spatial distribution of roughness values in SRH-2D proposed-conditions model	29
Figure 22: Time series of upstream flow boundary condition: unnamed tributary	30
Figure 23: Time series of upstream flow boundary condition: West Fork Hoquiam River	31
Figure 24: Downstream boundary condition normal depth rating curve on West Fork Hoquiam River (composite $n=0.072$ and slope= 0.04)	31
Figure 25: Location of boundary conditions for the coincident peaks existing-conditions model.....	32
Figure 26: Location of boundary conditions for the tributary existing-conditions model	32
Figure 27: Location of boundary conditions for the coincident peaks proposed-conditions model.....	33
Figure 28: Location of boundary conditions for the tributary proposed-conditions model	33
Figure 29: HY-8 culvert parameters, existing conditions model.....	34
Figure 30: Locations of cross sections used for reporting results of existing conditions simulations.....	37
Figure 31: Longitudinal profile stationing for existing conditions	37
Figure 32: Existing-conditions water surface profiles, coincident peaks.....	39
Figure 33: Existing-conditions water surface profiles, tributary only.....	39
Figure 34: Typical upstream existing channel cross section (facing downstream), coincident peaks.....	40
Figure 35: Typical upstream existing channel cross section (facing downstream), tributary only.....	40

Figure 36: Existing-conditions present day 100-year velocity map (coincident peaks scenario)	41
Figure 37: Existing-conditions present day 100-year velocity map (tributary only scenario)	41
Figure 38: Locations of cross sections used for reporting results of natural conditions simulations	42
Figure 39: Natural-conditions water surface profiles, coincident peaks	44
Figure 40: Natural-conditions water surface profiles, tributary only	44
Figure 41: Typical upstream natural channel cross section (facing downstream), coincident peaks	45
Figure 42: Typical upstream natural channel cross section (facing downstream), tributary only	45
Figure 43: Typical upstream natural channel cross section (facing downstream), coincident peaks	46
Figure 44: Typical upstream natural channel cross section (facing downstream), tributary only	46
Figure 45: Natural-conditions predicted velocity map with cross-section locations for present day 100- year coincident peaks simulation	47
Figure 46: Natural-conditions predicted velocity map with cross-section locations for the present day 100-year tributary simulation	47
Figure 47: Reference channel-based design cross section for outside the culvert footprint	49
Figure 48: Comparison of design cross-section with a representative cross-section outside of the replacement structure footprint.....	49
Figure 49: Schematic of proposed channel planform (top) and cross-section (bottom) layout inside the culvert. If there is concern of future loss of bar material to downstream, the thickness of the cobble layer can be increased to the dashed line	51
Figure 50: Locations of cross sections used for reporting results of proposed PHD simulations.....	53
Figure 51: Longitudinal profile stationing for proposed conditions	53
Figure 52: Proposed-conditions water surface profiles, coincident peaks.....	55
Figure 53: Proposed-conditions water surface profiles, tributary only	55
Figure 54: Typical section upstream of proposed structure (facing downstream), coincident peaks	56
Figure 55: Typical section upstream of proposed structure (facing downstream), tributary only	56
Figure 56: Typical section within proposed structure (facing downstream), coincident peaks	57
Figure 57: Typical section within proposed structure (facing downstream), tributary only	57
Figure 58: Proposed-conditions predicted 100-year velocity map for coincident peaks scenario	58
Figure 59: Proposed-conditions predicted 2080 100-year velocity map for coincident peaks scenario ...	58
Figure 60: Proposed-conditions predicted 100-year velocity map for tributary only scenario.....	59
Figure 61: Proposed-conditions predicted 2080 100-year velocity map for tributary only scenario.....	59
Figure 62: Proposed-conditions predicted 100-year water surface elevations for 13 feet and 18 feet wide structures, tributary only scenario	61
Figure 63: Conceptual layout of key LWM and meander bars for habitat complexity.....	66
Figure 64: Existing and proposed 100-year water surface profile comparison, tributary only	67
Figure 65: Existing and proposed 100-year water surface profile comparison, coincident peaks.....	68
Figure 66: Water surface elevation change from existing (top) to proposed (bottom) conditions	69
Figure 67: Climate impacts vulnerability assessment of Olympic Region areas 3 and 4 (source: WSDOT 2011). Site location is indicated by star	71

Tables

Table 1: Recent major land cover composition upstream of culvert	3
Table 2: Native fish species potentially present within the project area	8
Table 3: Bankfull width (BFW) measurements	16
Table 4: Sediment properties upstream of project crossing	17
Table 5: USGS regression-based estimates of peak flow	23
Table 6: Local USGS gages used to evaluate bias in USGS regression predictions	23
Table 7: Manning's n hydraulic roughness coefficient values used in the SRH-2D model	28
Table 8: Hydraulic results for existing conditions within main channel	38
Table 9: Existing-conditions velocities at select cross sections for 100-year tributary simulation	38
Table 10: Hydraulic results for natural conditions within main channel	43
Table 11: Natural-conditions average velocities predicted for 100-year flood over floodplains and in main channel at select cross sections	43
Table 12: FUR determination	48
Table 13: Average main channel hydraulic results for proposed conditions upstream and downstream of structure (C=coincident peaks, T=tributary only)	54
Table 14: Proposed-conditions average velocities predicted for 100-year flood over floodplains and in main channel at select cross sections	54
Table 15: Predicted main channel velocities within 13 feet and 18 feet wide structures	61
Table 16: Parameters relevant to freeboard specification for proposed 13 feet wide replacement structure	62
Table 17: Comparison of observed and stable streambed, and proposed stream simulation and meander bar material grain size distributions	64
Table 18: Report summary	73

1 Introduction


To comply with *United States et al. vs. Washington et al.* No. C70-9213 Subproceeding No. 01-1 dated March 29, 2013 (a federal permanent injunction requiring the State of Washington to correct fish barriers in Water Resource Inventory Areas [WRIAs] 1–23), the Washington State Department of Transportation (WSDOT) is proposing a project to provide fish passage at the United States Highway 101 (U.S. 101) crossing of the unnamed tributary to the West Fork Hoquiam River at Mile Post (MP) 98.47. This existing structure on U.S. 101 has been identified as a fish barrier by the Washington Department of Fish and Wildlife (WDFW) and WSDOT Environmental Services Office (ESO) (site identifier [ID] 993702) and has an estimated 3,401 linear feet (LF) of habitat gain (WDFW 2021).

Per the injunction, and in order of preference, fish passage should be achieved by (1) avoiding the necessity for the roadway to cross the stream, (2) use of a full-span bridge, or (3) use of the stream simulation methodology. WSDOT evaluated the crossing using the stream simulation methodology.

The crossing is located in Grays Harbor County 9.5 miles north of Hoquiam, Washington, in WRIA 22. The highway runs in a north–south direction at this location and is about 60 feet (ft) from the confluence with the West Fork Hoquiam River. The West Fork Hoquiam River generally flows from north to south beginning upstream of the U.S. 101 crossing. The unnamed tributary (UNT) generally flows from northeast to southwest beginning approximately 4,000 feet upstream of the U.S. 101 crossing (see Figure 1 for the vicinity map).

The proposed project will replace the existing structure, an 80-foot long, and 3-foot concrete circular culvert with a concrete box culvert with a hydraulic opening of 13 feet. The proposed structure is designed to meet the requirements of the federal injunction using the stream simulation design criteria as described in the 2013 WDFW *Water Crossing Design Guidelines* (WCDG) (Barnard et al. 2013). This design also follows the WSDOT *Hydraulics Manual* (WSDOT 2019) with supplemental analyses as noted.

A draft Preliminary Hydraulic Design (PHD) report was prepared in 2020 by WSDOT and HDR Engineering, Inc. under Agreement Number Y-12374 between HDR and WSDOT Environmental Services Office. WSDOT received review comments on the draft PHD report from WDFW and the Quinault Indian Nation (QIN). As part of Kiewit’s Coastal-29 Team of the US 101/SR 109 Grays Harbor/Jefferson/Clallam, Remove Fish Barriers Project under a Progressive Design-Build (PDB) contract between Kiewit and WSDOT, Kleinschmidt Associates (KA) reviewed the draft PHD report, updated the hydraulic modeling and design, addressed WDFW and Tribe comments, and prepared this Draft Final PHD report using material in the draft PHD report as a starting point. Responses to WDFW and Tribe comments are included in Appendix J. While HDR’s original field observations and measurements, and selected figures have been retained in this report, all writing and analyses in the draft PHD report have been reviewed, edited, and updated where determined necessary.



Vicinity Map
US 101 Unnamed Tributary To WF Hoquiam River
 Mile Post 98.47
 WDFW ID 993702

Figure 1: Vicinity map

2 Watershed and Site Assessment

The existing site was assessed in terms of watershed, land cover, geology, floodplains, fish presence, observations, wildlife, and geomorphology. This was performed using desktop research including aerial photos; resources such as the United States Geological Survey (USGS), Federal Emergency Management Agency (FEMA), and WDFW; past records like observation, and fish passage evaluation; and site visits.

2.1 Watershed and Land Cover

The project stream is located in the southern foothills of the Olympic Mountains, approximately 9.5 miles north of Hoquiam, WA, and as a tributary of the West Fork Hoquiam River, drains to the west under U.S. 101. The watershed is generally forested, and the perimeter of the basin is encircled by existing logging roads. Light detecting and ranging (LiDAR) data indicates the presence of minor drainages, but no other major tributaries are present within the basin. Elevations in the basin vary from approximately 185 to 385 feet with a mean basin elevation of 320 feet and a mean basin slope of about 11.5 percent. Downstream of the crossing, the stream flows approximately 30 feet before joining the West Fork Hoquiam River as a left bank tributary. The West Fork Hoquiam River is joined by several additional tributaries before joining the East Fork Hoquiam River.

Land cover for this basin consists of primarily forest and scrub/shrub land. The 2016 National Land Cover Database (NLCD) map shows land cover to be mostly evergreen forest with dispersed regions of shrub, deciduous forest, and low-intensity development (Figure 2; Table 1). The Grays Harbor County Assessor's Office web mapping database indicates the stream flows through a parcel owned by a timber company. The entire basin has been logged at one time or another and is encircled with logging roads. Historic aerial imagery on Google Earth indicates that nearly all of the drainage was clearcut on the north side of the channel in the early 2000s, leaving a narrow riparian buffer strip. Future timber harvest is expected to follow Washington's Forest Practices Habitat Conservation Plan requirements involving wider buffer strips than was typical prior to 2005.

Table 1: Recent major land cover composition upstream of culvert

Land Cover Class	Basin Coverage (Percentage)
Evergreen forest	67
Deciduous forest	28.5
Low-intensity development	4.5




Figure 2: Land cover map (NLCD 2016). Approximate catchment area upstream of the culvert is depicted

2.2 Geology and Soils

The drainage basin is underlain entirely by Pleistocene Age, alpine glacial outwash, dated as younger pre-Wisconsinan in age as mapped at the 1:100,000 scale (Figure 3; Logan 2003; Washington Division of Geology and Earth Resources 2016; Washington State Department of Natural Resources (DNR) Geologic Information Portal. Logan (2003) describes this unit as consisting of sand and gravel, composed of sandstone and basalt derived from the core of the Olympic Mountains. Clasts comprising the deposit are generally moderately to well-rounded with characteristic red-orange weathering rinds. The grain size distribution (GSD) of the material is characteristically poorly to moderately sorted and the material is weathered to depths exceeding 12 feet.

No indicators of landslide activity were observed during the 7/13/2021 field visit. A boundary search conducted on August 2021 of the DNR landslide inventories and hazards (Washington Geological Survey, 2020a, 2020b) identified no landslide studies or landslide hazards within the watershed. The watershed's steep hillslopes are dominated by highly to moderately erodible Copalis and Le Bar soil types (Figure 4; NRCS 2012). The soil characterization and geological description suggest a source and potential supply of sands and gravels to the project stream.

According to a recent geotechnical boring on the east side of the US 101 shoulder, there is dense silty, sand with gravel at depth (below 159 ft Above Sea Level (ASL)), and a sandy elastic silt from elevation 159-166 feet ASL. From 166-172.5 feet ASL, were silty sands and gravels, topped with 7.3 feet of fill and asphalt. (WSDOT 2020). Our interpretation is that the project stream erodes its uplands composed solely of Pleistocene Alpine outwash and reworked alluvium.


2.3 Floodplains

The project is not within a regulatory Special Flood Hazard Area, which is the 1 percent or greater annual chance of flooding in any given year. The existing U.S. 101 culvert is located in Zone X (unshaded) based on FEMA Flood Insurance Rate Map (FIRM) 53027C0675D, effective date February 3, 2017 (Appendix A). An unshaded Zone X represents areas of minimal flood hazard from the principal source of flooding in the area and is determined to be outside the 0.2 percent annual chance floodplain. Maintenance records provided do not describe any historical flooding issues.

2.4 Site Description


The project stream is an unnamed left bank tributary to the West Fork Hoquiam River, which flows south towards Grays Harbor. The existing culvert was documented by WDFW to have an estimated 67 percent passability as controlled by slope and excessive velocities in the culvert, and is downstream of an estimated 3,400 feet of habitat (WDFW 2021). Habitat in the vicinity of the culvert and upstream appears to be primarily suitable for juvenile salmonids, and possibly adult resident salmonids, with an estimated 160 ft² of spawning habitat upstream. There are small patches of gravel present in hydraulically sheltered locations, but spawning habitat was not found within the project reach.

The structure has not been identified as a failing structure or with a status of chronic environmental deficiency. No maintenance problems have been noted by WSDOT for this culvert.



Geologic Map
US 101 Unnamed Tributary To WF Hoquiam River
 Mile Post 98.47
 WDFW ID 993702

Figure 3: Geologic map. Approximate catchment area upstream of the culvert is depicted



Soils Map
US 101 Unnamed Tributary
 Mile Post 98.47
 WDFW ID 993702

Figure 4: Soils map. Approximate catchment area upstream of the culvert is depicted

2.5 Fish Presence in the Project Area

The online databases for the Statewide Washington Integrated Fish Distribution (SWIFD) (2020) and WDFW SalmonScape and Priority Habitats and Species (PHS) data (WDFW 2020a, 2020b) do not indicate documented fish use upstream of the culvert. Rainbow trout, the resident form of steelhead (*Oncorhynchus mykiss*), are presumed present (SWIFD 2020). The project crossing, however, is within approximately 30 feet of the West Fork Hoquiam River, which is documented to have Coho Salmon (*O. kisutch*), steelhead, and coastal Cutthroat Trout (*O. clarkii clarkii*) (SWIFD 2020; WDFW 2020a, 2020b; StreamNet 2020), and are assumed to be able to use habitat upstream of the culvert (WDFW 2021; Table 2).

Coho Salmon spend their first year rearing in fresh water and can disperse throughout tributaries and off-channel habitats. Suitable coho rearing habitat is present in the project reach and Coho overwintering and rearing is presumed.

Steelhead that inhabit the watershed are part of the Southwest Washington distinct population segment (DPS) and are not currently listed under the Endangered Species Act (ESA). Rearing and overwintering juvenile steelhead may potentially disperse upstream into the unnamed tributary by the project crossing.

Coastal Cutthroat Trout are widespread throughout small streams in Washington, prefer the uppermost portions of these streams, and can be anadromous and rear in streams for 2 to 3 years or be resident and remain entirely in fresh water (Wydoski and Whitney 2003). It is possible that Cutthroat Trout may also use habitat upstream of the culvert.

A single small salmonid fish (~2 inches) was observed near the culvert inlet, upstream of U.S. 101 during a field visit performed by HDR staff on May 14, 2020.

Table 2: Native fish species potentially present within the project area

Species	Presence (presumed, modeled, or documented)	Data source	ESA listing ^a
Coho Salmon (<i>Oncorhynchus kisutch</i>)	Presumed (documented in West Fork Hoquiam River)	SWIFD 2020, WDFW 2020a, WDFW 2020b	Not warranted
Southwest Washington DPS ^b steelhead (<i>Oncorhynchus mykiss</i>)	Presumed (documented in West Fork Hoquiam River)	SWIFD 2020, WDFW 2020a, WDFW 2020b	Not warranted
Coastal Cutthroat (<i>Oncorhynchus clarkii clarkii</i>)	Presumed (documented in West Fork Hoquiam River)	SWIFD 2020, WDFW 2020b	Not warranted

a. ESA = Endangered Species Act.

b. DPS = distinct population segment.

2.6 Wildlife Connectivity

The one mile segment that the culvert lies within is ranked Medium priority for Ecological Stewardship and Low priority for Wildlife-related Safety. Adjacent segments to the north and south ranked Low. WSDOT has determined that in order to be eligible for a habitat connectivity analysis, fish barrier correction projects must fall in or adjacent to a high priority road segment, or a project team member can request the analysis. No changes to design appear to be needed to accommodate wildlife crossing.

2.7 Site Assessment

A site assessment was performed of fish habitat conditions, hydraulic and geomorphic characteristics, and the culvert based on field visits, WDFW's barrier inventory report (WDFW 2021), and a WSDOT survey. An initial visit occurred in 2020, with subsequent visits postponed until 2021 after the Covid-19 pandemic had begun to subside.

2.7.1 Data Collection

Site visits were performed on four occasions to collect data and observe conditions and characteristics influencing the hydraulic design:

- HDR visited the project site on May 14, 2020, to collect pertinent information to support development of an initial design, including bankfull width (BFW) measurements, and characterizations of instream fish habitat and floodplain conditions. Channel substrates, large wood accumulations and floodplain vegetation were characterized.
- Kleinschmidt-R2 and Kiewit visited the site on June 1, 2021 to corroborate the initial data collection findings, review the representativeness of the BFW and channel substrate measurements, and identify additional data collection needs.
- Kleinschmidt-R2 and Kiewit visited the site on June 16, 2021 to collect a bulk substrate sample, measure the hydraulic effect of natural downstream in-channel flow obstructions as it would affect hydraulic modeling predictions, and measure the typical size of mobile wood pieces upstream of the culvert as they would affect the determination of minimum freeboard requirements.
- Kleinschmidt-R2 and NHC visited the site on July 13, 2021 to support an evaluation of the long term vertical stability of the channel.

Field reports are presented for each visit in Appendix B.

WSDOT also surveyed the site in March 2020. The survey extended approximately 200 feet upstream of the culvert, 100 feet downstream of the culvert, and a total roadway survey length of 1,500 feet. The reach surveyed comprises the project reach within which most data were collected, and observations made for use in developing the design. Survey information included break lines defining stream bank toes and tops and overbank areas along the channel. The data were used to generate hydraulic models and evaluate geomorphology during development of the hydraulic design.

2.7.2 *Existing Conditions*

2.7.2.1 *Culvert*

The existing structure is an 80 feet long, 36-inch diameter round concrete pipe with a gradient of approximately 1.7 percent (WDFW 2021). No local constraints, infrastructure, or obvious signs of maintenance activity were observed in the immediate vicinity of the project site during site visits. The culvert inlet invert is approximately 2 to 3 inches above the channel thalweg at a pool tail, whereas the culvert outlet is countersunk (Figure 5). The stream banks are approximately 2 feet tall and vertical near the culvert inlet, and approximately 2 to 3 feet tall near the outlet.



Figure 5: Culvert inlet (left) and outlet (right)

2.7.2.2 *Stream*

The project stream enters the West Fork Hoquiam River (Figure 6) approximately 30 feet downstream of the culvert, at roughly a 90-degree angle. There is a log with rootwad situated at the confluence with the West Fork Hoquiam River that splits flows within the tributary channel as it enters the West Fork Hoquiam River (Figure 7).

The West Fork Hoquiam River is a substantially larger channel than the project stream and backs water up to the culvert during high flow. The mainstem channel is shallow above the confluence and transitions to a deep pool downstream. The banks of the West Fork Hoquiam River are approximately 3 feet high and have mature trees growing on them; additionally, the left bank upstream in the West Fork Hoquiam River is composed of several logs. A large (36-inch diameter) fallen conifer spans the West Fork Hoquiam River at the confluence, and its rootwad has been undercut by a small side flow from the project tributary. The streambed material in the river is composed primarily of sand and small gravel.

The project stream banks are approximately 1 foot high near the confluence. Bank materials are soft and silty and are overgrown with shrubs, ferns, and grass. No active bank erosion was observed in either the project stream channel or the mainstem during site visits. Some smaller trees roughly 3 inches in diameter are set back from the tributary by about 15 feet. The channel material is primarily silts and fines, with some gravel and sand present. Woody material was observed frequently in the channel. Upstream of the confluence by approximately 10 or 15 feet, a second woody material jam of sediment

and woody material is lodged on several posts within the stream. At this upstream jam, the water surface drops between approximately 1-2 feet. The streambed material between the culvert and river is composed of primarily fine sand and silt.



Figure 6: West Fork Hoquiam River



Figure 7: Rootwad log in project stream

The channel bed material upstream of the culvert is primarily sand and silt with some larger gravels present as pockets. Banks consist of mud and silt with riparian vegetation of shrubs and ferns. Larger trees are set back from the channel by approximately 15 feet and their branches grow over the channel. There is a drop in the water surface profile of about 6 inches over a natural cross-channel log located approximately 25 feet upstream of the culvert inlet (Figure 8). Upstream of the log, the channel is abutted by a small floodplain. The banks are soft with organic litter and moss. The channel material in this reach is composed primarily of gravels and fines, and there is substantially more woody material in the channel than downstream of the culvert. Riparian vegetation includes shrubs with some trees along the channel margin. There are multiple locations upstream of the log weir where woody debris is racked in the channel and the stream flows over and under various sized logs (Figure 9). Stream banks are mostly vertical, up to 4 feet in height in places with live trees and other vegetation along the channel margins (Figure 10). There are several large diameter trees lying across the channel where the channel has widened and scoured locally.



Figure 8: Natural log weir



Figure 9: Examples of embedded and channel spanning logs upstream of the culvert



Figure 10: Example of a vertical bank with vegetation

2.7.2.3 Floodplain

The channel downstream of the culvert flows within the floodplain of the West Fork Hoquiam River. The project stream appears to have little influence on overbank flows compared with the mainstem.

Upstream of the culvert, the channel is not entrenched, where there is a defined bankfull channel with a narrow floodplain. The surface of the floodplain is irregular in morphology, not densely vegetated, and interspersed with fallen trees and woody debris.

2.7.3 Fish Habitat Character and Quality

Upstream of the U.S. 101 crossing, the stream flows through a mixed forest composed primarily of alder (*Alnus rubra*), western hemlock (*Tsuga heterophylla*), and Douglas fir (*Pseudotsuga menziesii*). There is a dense shrub understory with native species including salmonberry (*Rubus spectabilis*), vine maple (*Acer circinatum*), salal (*Gaultheria shallon*), and sword fern (*Polystichum munitum*). The banks in the upstream reach next to the culvert inlet were topped by a dense shrub layer, then the understory becomes much more open upstream where the forest canopy is denser. The streambanks were generally low, with few incisions or undercuts.

The mature forest and shrub cover provides shading, nutrient inputs, and some potential for local LWM recruitment. LWM is important in western Washington streams in that it provides cover for fish and contributes to stream complexity, which is beneficial to salmonids. There were five places where logs and woody material were present in the stream channel and banks, and a total of 14 key pieces of LWM. These logs ranged from 6 to 48 inches in diameter. Smaller woody material including small branches and twigs in the streambed was also prevalent throughout the reach. These logs and woody material provide instream habitat cover and complexity for use by juvenile salmonids for rearing and overwintering.

Instream habitat within the project reach consists of predominantly shallow glides and riffles with fines and embedded gravel substrates, and limited pool habitat. Small scour pools form around flow obstructions. The paucity of pools and instream habitat complexity does not provide abundant rearing habitat, but juvenile Coho and possibly juvenile steelhead could still use the stream for some rearing and overwintering habitat, particularly during higher flows in the mainstem downstream.

The downstream reach is a short, 30-foot-long reach between the culvert outlet and the confluence with the West Fork Hoquiam River. The riparian vegetation in this area is dominated by shrubs and forbs as part of the road prism for U.S. 101. At the West Fork Hoquiam River, there are some alders and a few fir trees along the left bank where the unnamed tributary confluence is located, and large cedars (*Thuja plicata*) on the opposite bank. The riparian corridor is constrained on the left bank of the stream because of its proximity to the highway. There is a dense shrub understory with native species including salmonberry (*Rubus spectabilis*), willows (*Salix spp.*), Devils club (*Oplopanax horridus*), sedges, and non-native species including Himalayan blackberry (*Rubus armeniacus*). The immature forest canopy provides little shading over the tributary. The shrub cover provides nutrient inputs, and some cover and shading along the banks.

The substrate in the downstream reach is composed almost entirely of fines, small gravel, and organic material. This instream habitat is not suitable for spawning for salmonid species, but does provide some potential rearing and migratory habitat. There is little instream habitat complexity, and pools and cover

are lacking in the downstream reach. There was one small scour pool at the confluence along the right bank where a log embedded in the bank was undercut. The lack of pools and instream habitat complexity does not provide good rearing habitat, but the project reach still provides some off-channel habitat from the West Fork Hoquiam River and migratory habitat as access to the tributary upstream.

2.8 Geomorphology

Geomorphic information provided for this site includes selection of a reference reach, the basic geometry and cross sections of the channel, stability of the channel both vertically and laterally, and various habitat features.

2.8.1 Reference Reach Selection

The reach starting approximately 150 feet upstream of the culvert (Figure 11) was selected as most representative of the natural stream channel with the least anthropogenic influence. The reach downstream of the culvert was not considered a suitable reference because it experiences backwater from the West Fork Hoquiam River. The reference reach has an approximate average channel gradient of 2.2 percent. The reference reach was relied on primarily for measuring bankfull dimensions for informing the design of the hydraulic opening width and the cross-section morphology of the constructed channel outside of the replacement structure footprint. The reference reach morphology was not used to design cross-section shape and planform underneath the replacement structure because vegetation controlling bank stability cannot generally grow there.

2.8.2 Channel Geometry

Channel planform upstream of the existing culvert is characterized by a single thread meandering channel with a distinct bankfull morphology and floodplain. The channel meanders through several sharp bends formed in conjunction with immovable large wood and the adjacent hillslope. LWM is present in the channel and on the channel banks. The short reach of channel between the culvert and West Fork Hoquiam River is narrower than upstream. Woody material pieces are present in the channel, but are smaller in size than in the upstream reach. Channel morphology is judged to be generally stable, consistent with Stage I of Schumm et al.'s (1984) Channel Evolution Model.

Bankfull width (BFW) was measured with a tape at three locations in 2020, and determined at two other locations in 2021 based on surveyed cross-section profiles, upstream of the crossing within the reference reach (Figures 11 and 12; Table 3). The measured BFWs resulted in a design average BFW of 6.7 feet. As an independent check, the BFW estimate based on the WCDG regression equation for high-gradient, coarse-bedded streams in western Washington was 8.1 ft, based on the basin area and mean annual precipitation (see Section 3; Barnard et al. 2013). In addition, WSDOT also surveyed cross-sections at four other locations upstream of the culvert, above the influence of the West Fork Hoquiam River, as part of data collection for developing the hydraulic models (Figure 13). Station (STA) 2+15 was located within the reference reach. The cross-sections are characterized by vertical banks about 1.5 to 2.0 feet in height, a defined channel with a flat right floodplain, and a sloped left floodplain. Channel BFWs are around 8 feet or less. The width-to-depth ratio measured at STA 2+15 is approximately 4.5:1. The QIN visited the site after the 2020 BFW measurements were made, and measured different, larger

widths. An average value of 9 feet was proposed. In subsequent discussions between WSDOT, QIN, and WDFW, a design value of BFW = 9.0 ft consistent with QIN measurements was selected (Table 3).




Figure 11: Reference reach and locations of BFW measurements and substrate sampling




Figure 12: Cross-section profiles surveyed in 2021 for BFW determination




Figure 13: WSDOT's surveyed cross-section profiles upstream of the culvert

Table 3: Bankfull width (BFW) measurements

BFW #	Width (ft)	Included in Average	Concurrence notes
1	7.7	Yes	QIN Measured 9 ft
2	8.3	Yes	QIN Measured 10 ft
3	6.1	Yes	QIN – Do not include, not representative
4	6.4	Yes	New measurement based on cross-section profile
5	5.0	Yes	New measurement based on cross-section profile
Average	6.7		BFW=9 ft accepted by Co-Managers, June 9, 2021

2.8.3 Sediment

During the May 2020 site visit, a single Wolman pebble count was performed approximately 150 feet upstream of the culvert inlet within the reference reach. Additional pebble counts were not performed at the time based on reasoning that the existing streambed material grain size distribution was clearly finer than WSDOT's Standard Streambed Sediment, which was anticipated to be specified in the design. Upon further review, a sieve sample was subsequently collected from a distinct gravel deposit in June 2021, to provide an indication of the coarsest sediments that could be transported to the replacement structure. The locations of the sampling are indicated in Figure 11. The grain size distribution characteristics are summarized in Table 4. The largest sediment size in this reach observed was 3.5 inches (median axis diameter).

Table 4: Sediment properties upstream of project crossing

Particle size	Pebble Count Diameter (in)	Pebble Count Diameter (mm)	Sieve Sample Diameter (in)	Sieve Sample Diameter (mm)
D₁₆	0.1	3	0.1	3
D₅₀	0.2	5	1.0	26
D₈₄	0.4	10	1.9	47
D₉₅	0.8	20	2.3	59
D_{max}	3.5	89	-	-

2.8.4 Vertical Channel Stability

Vertical channel stability was assessed considering land use, longitudinal channel elevation profiles of the project stream and West Fork Hoquiam River, topographic models, and field observations on July 13, 2021. It may be assumed that historical land use in the watershed caused changes in sediment supply, wood loading, and runoff to a greater extent than what may be expected in the future, for several reasons. First, there is a low potential of landslides or debris flow type sediment delivery in the watershed (Section 2.2). Historical logging within the riparian zone and clearcut logging likely created historic spikes in sediment supply and greater runoff. With more conservative timber harvest practices and associated protective buffer width requirements in effect since 2005, future sediment yield is expected to decline and return to a lower background level.

Longitudinal profiles were developed from 2019 LiDAR data (Figure 14; USGS and Quantum Spatial 2019). 2020 survey data collected by WSDOT indicates that the channel elevations in the LiDAR data profile are higher than actual, but the bias appears to be consistent away from the road prism. The profiles were used to identify significant landmarks and breaks in the channel gradient along the tributary and West Fork Hoquiam River that would influence spatial variation in sediment transport and deposition patterns. The channel upstream of the culvert is generally steep (1.8%) and appears to be a transport reach. The gradient drops significantly at the culvert (0.3%), and then increases to 7.1% over the short distance between the culvert and the West Fork Hoquiam River. At the confluence, the West Fork Hoquiam River has a gradient of 0.9%, but the lack of deposits from the project stream suggests the sediment transport capacity of the West Fork Hoquiam is sufficient to carry away material delivered from the project stream. In general, the profile depicted in Figure 14 suggests that aggradation is less

likely than degradation, where the constructed channel may regrade to be in line with the upstream grade. The maximum amount of degradation based on extending the upstream profile downstream is approximately 2 feet at the outlet, and less than -0.5 feet at the inlet (cf Figure 14).

The break in gradient at the crossing would be expected to be associated with aggradation of gravel material over the long term. Finer grained material is likely to be transported to the short reach between the culvert and the West Fork Hoquiam River, and washed downstream by high flows and overbank flows in both channels. The maximum amount of localized aggradation associated with gravel deposition would be expected to scale with the height of the tributary's streambanks or around 1-1.5 feet. Assuming the channel is filled completely with gravel, additional gravel would be expected to form a wide depositional fan. Given no such fan is seen presently, there is a defined channel morphology, and gravel transport from upstream is not extensive, it is inferred that future channel aggradation in the vicinity of the crossing can be expected to be less than 1.5 feet.



Figure 14: Watershed-scale longitudinal profile and gradients of the Middle Fork Hoquiam River and project stream; plot includes comparison of LiDAR with WSDOT survey data; dashed red line is upstream grade extended downstream

While there is limited potential for localized channel aggradation upstream of US 101 currently under existing conditions, the possibility exists that potential future profile adjustments downstream in the West Fork Hoquiam River could lead to profile adjustments in the project stream in the vicinity of the crossing, where the adjustment could be associated with degradation or aggradation depending on circumstances as described below. The overall grade lower down in the project stream appears to be influenced by grade control processes in the West Fork. In particular, there are presently a series of 3 wood-forced steps in the West Fork, with the first step located 100 ft downstream of the culvert.

2.8.4.1 Channel Degradation Associated with Changes in the West Fork Hoquiam River

The West Fork Hoquiam River profile does not indicate any significant discontinuities, and the confluence is upstream of another reduction in grade (Figure 14). In section 2.8.5, no historical lateral migration was observed, and the potential for avulsion was deemed unlikely. However, the wood steps downstream of the confluence could deteriorate and possibly wash out, lowering the grade control up to 1.0 foot or a low of 170.6 feet. Because the West Fork Hoquiam River sets the fundamental base level grade control for the creek, lowering of the mainstem grade would propagate upstream, 100 feet on the mainstem and 30 feet up the tributary. The average gradient of the West Fork is 0.9%. The minimum slope observed upstream of the crossing (1.8%) provides a conservative estimate of the expected regrade slope and so this scenario sets the minimum plausible channel grade at the downstream side of the crossing by extending the profile as discussed above, down to approximately elevation 172.1 ft. Because this elevation is based on several conservative additive assumptions, it is relatively unlikely that the stream bed will lower to this elevation over the design life of the culvert. This amount of degradation is especially unlikely given hydraulic modeling of flood flow for both systems; this shows a significant backwater control from the West Fork (source), that may reduce the propensity for flows in the project stream to cause incision during coincident high flow events.

2.8.4.2 Channel Aggradation Associated with Changes in the West Fork Hoquiam River

The West Fork Hoquiam River watershed is approximately an order of magnitude larger than the project stream at the crossing, and the channel is accordingly wider and can transport LWM. There is a possibility, albeit what is judged to be a relatively low probability, that a channel spanning log jam on the West Fork Hoquiam River would cause aggradation at the crossing. Steps over spanning, buried wood in the project stream bottom indicate that at least 1 ft of aggradation has occurred over such features in the past. Typical guidance for profile variability in larger, gravel bed rivers in Western Washington (Rapp and Abbe 2003) indicates that at least 2m (7 ft) of aggradation should be considered possible, but this scales with the size of wood transported and the transport and deposition of significant quantities of large gravel. The West Fork does not appear to transport significant volumes of coarse gravel, or large diameter logs. Moreover, the most likely location for racking logs downstream is where the wood steps are located, where the West Fork Hoquiam River would have to aggrade more than 3 feet locally before impacting the project stream at the US 101 crossing. Given the evidence of some historic local incision of 1.5 feet in the river downstream, the presence of a defined channel cross-section downstream of the crossing that is not substantially shallower than upstream, and the generally consistent grade of the West Fork, the risk of significant aggradation is considered relatively low at this site.

2.8.5 **Channel Migration**

Channel migration was assessed for both the project stream and the West Fork Hoquiam River based on topography and field observations. The project stream and West Fork are generally too small and canopy too thick for aerial photography to be of use for evaluating migration history.

2.8.5.1 *Project Stream*

While the stream is markedly sinuous upstream of the culvert, it does not exhibit signs of significant channel meandering or avulsion, with the planform constrained by large wood, established trees growing in the banks, and the adjacent hillside. Hydraulic modeling indicates that the 2-year flood is generally confined in much of the reference reach upstream of the crossing, with no floodplain flow paths engaged (Appendix C). Downstream of the culvert, velocities in the project stream are low during floods because of backwater from the West Fork Hoquiam River. Consequently, the project stream is not expected to exhibit significant channel migration sufficient to influence the design.

2.8.5.2 *West Fork Hoquiam River*

While there were no signs of significant channel migration by the West Fork Hoquiam River, the dominant shrub cover along the streambank and floodplain between the river and the culvert would not be expected to prevent bank erosion along the river left bank in the vicinity of the confluence. Hydraulic sheltering is provided by mature trees growing on the left bank and floodplain upstream, but additional protection against erosion at the confluence could be provided through strategic large wood placement along the right bank of the tributary channel.

2.8.6 **Riparian Conditions, Large Wood, and Other Habitat Features**

The banks in the upstream reach proximal to the culvert inlet are vegetated with a dense shrub layer. The understory becomes more open moving upstream, where the forest canopy is denser. The riparian corridor consists of a mixed mature forest composed primarily of alder, western hemlock, and Douglas fir. There is a dense shrub understory with native species including salmonberry (*Rubus spectabilis*), vine maple (*Acer circinatum*), salal (*Gaultheria shallon*), and sword fern (*Polystichum munitum*). The mature forest and shrub cover provides good shading, nutrient inputs, and some potential for LWM recruitment. Measurements of mobile pieces upstream of the culvert indicates that pieces longer than about 7 feet and thicker than about 5 inches in diameter are not transported far and become racked up on larger pieces of wood and brush. Trees that fall into or across the channel remain generally in place.

There were five places where logs and woody material were noted in the stream channel and banks, and a total of 14 key pieces of LWM. These logs ranged from 6 to 48 inches in diameter. A small cascade is formed by several pieces of LWM in the streambed near the midpoint of the surveyed reach.

Downstream of the crossing, a short reach joins the West Fork Hoquiam River within approximately 30 feet of the culvert outlet. The riparian corridor is predominantly roadside shrub and forb vegetation because of its proximity to the U.S. 101 road prism. The riparian corridor is constrained on the left bank of the stream because of its proximity to the highway. There is a dense shrub understory with native species including salmonberry (*Rubus spectabilis*), willows (*Salix spp.*), Devils club (*Oplopanax horridus*), sedges, and non-native species including Himalayan blackberry (*Rubus armeniacus*). At the West Fork

Hoquiam River, there are some alders and a few fir trees along the left bank where the unnamed tributary confluence is located, and large cedars (*Thuja plicata*) on the opposite bank.

An embedded rootwad located on the left bank at the confluence is undercut by flows from the unnamed tributary that pass through a small opening underneath. A natural log weir spans the channel of the West Fork Hoquiam River just downstream of the confluence with the unnamed tributary, and forms a large pool. This pool is located at the confluence, and a large fallen tree is lying across the banks above the wetted channel.

WDFW completed a physical survey in 2005 at the site (WDFW 2005). No beaver dams or beaver sign was observed upstream and downstream of the crossing during the WDFW survey and in any of the site field visits.

3 Hydrology and Peak Flow Estimates

The project stream drains an ungaged basin, with no long-term historical flow data available. No hydrologic studies, models, or reports were found that summarized peak flows in the basin. Consequently, USGS regression equations (Mastin et al. 2016; Region 4) were used to estimate peak flows at the U.S. 101 crossing. Inputs to the regression equation included basin size and mean annual precipitation. The unnamed tributary has a basin area of 0.22 square mile above the culvert and a mean annual precipitation within the basin of 102.8 inches (PRISM Climate Group 2019). LiDAR data acquired along with the survey data directly from WSDOT. The catchment was delineated using Arc Hydro to determine drainage areas and precipitation values as inputs for the regression equations.

The hydraulic model extents also includes the confluence with the West Fork Hoquiam River and as a result it was necessary to estimate peak flows for the West Fork River. Similar to the project stream, peak flows were estimated for the West Fork Hoquiam River using the USGS regression equations. Just upstream of confluence, the West Fork Hoquiam River has a delineated watershed area of 1.87 square miles and a mean annual precipitation of 105.1 inches (PRISM Climate Group 2019).

The resulting regression estimates (Table 5) were evaluated for potential sub-regional bias by comparing regression predictions against estimates derived at selected stream gages in the area using available flow records. A Washington Department of Ecology gage was identified from the Wishkah River, but only USGS gages were found with a sufficiently long period of record (>20 years) in the area to permit evaluating the larger predicted flood peaks (Table 6).

Peak flow data were analyzed for each gage following the Bulletin 17B methodology for peak flow frequency analysis, using the Hydraulic Engineering Center's Statistical Software Package (HEC-SSP) version 2.2. HEC-SSP uses the Log Pearson Type III distribution for annual peak flows on unregulated streams, fit by the Method of Moments. Distribution parameters were estimated for the 2-, 10-, 100-, and 500-year return intervals based on moments of the sample data (site-specific). Adjustments were made for non-standard data, low outliers, and historical events. The resulting peak flow estimates were compared against the regression estimates using the equations in Mastin et al. (2006), where drainage area and mean annual precipitation estimates were determined using USGS' StreamStats web application. The ratio of gage-based to regression-based estimates was then plotted against drainage area (Figure 15). The results indicate that the regression estimates for smaller basins may be generally comparable to or higher than would be derived using gage data. As corroboration, a modeling exercise performed for Culvert ID 993704 using the MGS Flood model indicated that the regression estimates for a similarly sized, nearby drainage area were higher than values estimated based on a more direct simulation of stormwater rainfall-runoff processes. The regression estimates accordingly appear to be more conservative.

Consequently, the regression estimates in Table 5 were used in design development, to provide a safety factor when designing for flood conveyance, freeboard, channel stability, and scour. The 2080 predicted 100-year flow determination provides context for addressing climate change, as described in Section 7.2.

Summer low-flow conditions are unknown and high/low fish passage design flows are not included in this analysis. The stream was observed to still be flowing in mid-August 2021.

Table 5: USGS regression-based estimates of peak flow

Mean recurrence interval (MRI) (years)	Unnamed tributary USGS regression equation (Region 4) (cfs)	West Fork Hoquiam River USGS regression equation (Region 4) (cfs)	Regression standard error (percent)
2	21.7	159	52.5
10	37.8	276	50.5
25	45.6	333	51.7
50	51.6	378	52.9
100	58.4	428	54.2
500	72.2	533	58.0
2080 predicted 100	63.2	467	NA

Table 6: Local USGS gages used to evaluate bias in USGS regression predictions

Station #	Gage Name	Years of Record
12039005	Humptulips River Below Hwy 101	2002-2018
12036000	Wynoochee River Above Save Creek Near Aberdeen, WA	1952-2018
12035500	Wynoochee River at Oxbow Near Aberdeen, WA	1925-1952
12035450	Big Creek near Grisdale, WA	1972-1996
12035400	Wynoochee River near Grisdale, WA	1965-2018
12039050	Big Creek near Hoquiam, WA	1949-1970
12039100	Big Creek Tributary near Hoquiam, WA	1949-1968




Figure 15: Ratio of gage-based flood peak magnitudes vs. regression-based estimates, plotted against drainage area

4 Hydraulic Analysis and Design

The hydraulic analysis of the existing and proposed crossing was performed using the United States Bureau of Reclamation's (USBR's) SRH-2D Version 3.0 computer program, a two-dimensional (2D) hydraulic and sediment transport numerical model (USBR 2017). Pre- and post-processing for this model was completed using SMS Version 13.1.11 (Aquaveo 2021).

Three scenarios were analyzed for determining stream characteristics for the unnamed tributary with the SRH-2D models: (1) existing conditions with a 3-foot concrete culvert through the crossing, (2) estimated natural conditions with the roadway embankment and culvert removed, and (3) future conditions with the proposed 13-foot hydraulic opening.

Because of the proximity of the crossing to the confluence with the West Fork Hoquiam River, the crossing may be subject to backwater from the mainstem during flood events. Accordingly, two sets of alternate scenarios were run for each existing-, proposed-, and natural-conditions model. The first set of simulations, herein described as the *tributary scenario*, includes one flow time series upstream boundary condition on the unnamed tributary with no flow present on the West Fork. The second set of simulations, herein described as the *coincident peaks scenario*, describes a set of scenarios that includes flow time series upstream boundary conditions on the unnamed tributary and the West Fork Hoquiam River. The six simulations run for the existing-, proposed-, and natural-conditions models are described as *2-year tributary*, *100-year tributary*, *500-year tributary*, *2-year coincident*, *100-year coincident*, and *500-year coincident*. Model simulations were run for a sufficiently long duration until the results stabilized across the model domain.

4.1 Model Development

This section describes the development of the model used for the hydraulic analysis and design.

4.1.1 Topographic and Bathymetric Data

The channel geometry data in the model were obtained from the MicroStation and InRoads files supplied by the Project Engineer's Office (PEO), which were developed from topographic surveys performed by WSDOT prior to March 13, 2020. The survey data, representing channel features and sections of U.S. 101, were supplemented with LiDAR data by WSDOT. Detailed channel survey extended 70 feet downstream of the crossing and 200 feet upstream of the crossing. Proposed channel geometry was developed from a proposed grading surface created initially by HDR. All survey and LiDAR data are referenced to the North American Vertical Datum of 1988 (NAVD88) using U.S. Survey feet.

4.1.2 Model Extent and Computational Mesh

The hydraulic model upstream and downstream extents start and end with LiDAR beyond the detailed topographic survey data for the West Fork Hoquiam River and unnamed tributary. The detailed survey data were combined with the LiDAR by WSDOT, and started approximately 200 feet upstream of the existing culvert inlet measured along the channel centerline. The upstream domain limit was selected to be far enough upstream to include the reference reach and allow the model to simulate lateral velocity

variation in the areas of concern. Two to three floodplain widths of additional LiDAR should be applied upstream of survey data if data were available. A similar approach would be ideally applied to the downstream boundary condition. However, the survey data only extend about 70 feet downstream of the confluence of the unnamed tributary with the West Fork Hoquiam River. LiDAR data in the channel were 2 to 3 feet higher than the surveyed channel bottom, indicating that the channel thalweg would not be estimated reasonably with LiDAR data downstream of the survey. For this reason, the downstream extent of the model is located roughly at the end of the survey extent, about 60 feet downstream of the crossing.

The computational mesh elements are a combination of patched (quadrilateral) and paved (triangular) elements, with finer resolution in the channel and larger elements in the floodplain. The existing conditions model mesh covers a total area of 86,999 square feet (SF) with 7,020 quadrilateral and 56,067 triangular elements (Figure 16). The natural conditions model mesh covers a total area of 86,986 SF, with 6,284 quadrilateral, and 57,484 triangular elements (Figure 17). The proposed PHD mesh covers a total area of 81,016 SF, with 6,368 quadrilateral and 49,919 triangular elements (Figure 18).




Figure 16: Existing-conditions computational mesh with underlying terrain




Figure 17: Natural-conditions computational mesh with underlying terrain




Figure 18: Proposed-conditions computational mesh with underlying terrain

4.1.3 Materials/Roughness

Manning's n values were estimated for the natural channel and floodplain of the project stream using the Cowan method based on site observations (Arcement and Schneider 1989; see Appendix G). A channel value was also estimated for the West Fork Hoquiam River. The resulting values were consistent with standard engineering values for 1-D simulations (Barnes 1967). The value for the culvert was estimated using the same reference, with a base value of $n=0.035$ for a gravel-cobble mix, and with 0.01 added to account for low profile bedforms that will be part of the final design (see Section 4.4). The resulting 1-D values were then adjusted down by 10 percent to reflect generally expected reductions when moving to a 2-D model parameterization (Robinson et al. 2019; Table 7). Figures 19, 20, and 21 depict the spatial distribution of hydraulic roughness coefficient values for the existing, natural, and proposed condition scenarios, respectively.

Table 7: Manning's n hydraulic roughness coefficient values used in the SRH-2D model

Land cover type	Manning's n
Forest	0.095
Floodplain	0.095
Stream Channel	0.075
W. Fork Hoquiam River Channel	0.050
Paved roadway	0.020
Roadway Embankment/Irregular Fill	0.040
Within Proposed Crossing	0.041




Figure 19: Spatial distribution of roughness values in SRH-2D existing-conditions model




Figure 20: Spatial distribution of roughness values in SRH-2D natural-conditions model




Figure 21: Spatial distribution of roughness values in SRH-2D proposed-conditions model

4.1.4 **Boundary Conditions**

Model simulations were performed using time series discharges ranging from the 2-year to 500-year peak flow events summarized in Section 3. External boundary conditions were applied at the upstream and downstream extents of the model domain and remained the same between the existing-, natural-, and proposed-conditions runs. A time varied flow rate was specified at the upstream external boundary conditions for the project stream (Figure 22) and West Fork Hoquiam River (Figure 23). A normal depth rating curve was used to specify a flow dependent water surface elevation at the downstream boundary in the West Fork (Figure 24). A sensitivity analysis was performed during early model development of the effect of error in the downstream normal depth slope. This analysis determined that the water surface elevations and velocities at the downstream end of the crossing are not sensitive to the downstream boundary. The downstream boundary was accordingly placed such that the model results for the existing and proposed culvert conditions were influenced the least by the downstream boundary condition. The locations of each boundary condition for the existing and proposed conditions for each case are identified in Figures 25-28.

An HY-8 internal boundary condition was specified in the existing-conditions model to represent the existing circular concrete culvert crossing (Figure 29). The existing crossing was modeled as a 3-foot-diameter circular pipe within HY-8. A Manning's roughness of 0.012 was assigned to the culvert. The culvert was assumed to be unobstructed and free from any stream material within the barrel. The HY-8 internal boundary conditions were removed for the natural and proposed scenarios. To represent the edge of the proposed structure, a slip boundary was added outside of the proposed channel within the roadway. The addition of this boundary condition to all proposed conditions simulates a more realistic interaction between flow and the edge of proposed structure.




Figure 22: Time series of upstream flow boundary condition: unnamed tributary




Figure 23: Time series of upstream flow boundary condition: West Fork Hoquiam River




Figure 24: Downstream boundary condition normal depth rating curve on West Fork Hoquiam River (composite $n=0.072$ and slope=0.04)




Figure 25: Location of boundary conditions for the coincident peaks existing-conditions model




Figure 26: Location of boundary conditions for the tributary existing-conditions model




Figure 27: Location of boundary conditions for the coincident peaks proposed-conditions model




Figure 28: Location of boundary conditions for the tributary proposed-conditions model

Crossing Data - Crossing_993702

Crossing Properties

Name: Crossing_993702

Parameter	Value	Units
DISCHARGE DATA		
Discharge Method	User-Defined	
Discharge List	Define...	
TAILWATER DATA		
Channel Type	Trapezoidal Channel	
Bottom Width	5.000	ft
Side Slope (H:V)	3.000	_:1
Channel Slope	0.0170	ft/ft
Manning's n (channel)	0.040	
Channel Invert Elevation	172.518	ft
Rating Curve	View...	
ROADWAY DATA		
Roadway Profile Shape	Constant Roadway Elevation	
First Roadway Station	0.000	ft
Crest Length	3.000	ft
Crest Elevation	182.601	ft
Roadway Surface	Paved	
Top Width	40.000	ft

Culvert Properties

993702

Add Culvert

Duplicate Culvert

Delete Culvert

Parameter	Value	Units
CULVERT DATA		
Name	993702	
Shape	Circular	
Material	Concrete	
Diameter	3.000	ft
Embedment Depth	0.000	in
Manning's n	0.012	
Culvert Type	Straight	
Inlet Configuration	Grooved End Projecting	
Inlet Depression?	No	
SITE DATA		
Site Data Input Option	Culvert Invert Data	
Inlet Station	0.000	ft
Inlet Elevation	172.864	ft
Outlet Station	80.381	ft
Outlet Elevation	171.641	ft
Number of Barrels	1	

Help Click on any icon for help on a specific topic Low Flow AOP Energy Dissipation Analyze Crossing OK Cancel

Figure 29: HY-8 culvert parameters, existing conditions model

4.1.5 Model Run Controls

All simulations were run using similar model controls. Model control variables were adjusted for model stability and adequate runtime to reach steady state. Most simulations were stable with a 1 second timestep, however some required a 0.1 second timestep to reduce instabilities. The following controls were set:

- Start Time: 0 hours
- Time Step; 0.1, 0.5 or 1 second
- End Time: 9 hours
- Initial Condition: Dry

The end time was adjusted during model development so that the duration was long enough to achieve steady-state conditions. The model was started at approximately 0 hour, with an appropriate time step, and was truncated after 9 hours for each existing-, natural-, and proposed-conditions simulation. Simulations for all 100-year and 500-year events were run with either a 0.5 or 0.1-second time step to achieve better stability in the model results. All scenarios were run with an initial dry condition.

4.1.6 Model Assumptions and Limitations

The SRH-2D hydraulic model was developed to determine the minimum hydraulic structure opening, establish the proposed structure low chord elevation (and associated freeboard), and characterize hydraulic parameters used to design the crossing structure, streambed, and LWM. There are several

attributes of the data relied upon to develop the model that affect the resolution to which model output should be relied on. In particular, the survey data collected for developing the model terrain geometry were sufficient to capture macroscale variation in channel form and floodplain topography on the order of average channel width/depth/location and floodplain gradients. The spatial scatter of the survey point data was too coarse, however, to develop a model terrain capable of discerning an accurate and precise resolution of velocity distributions at smaller microtopographic scales, precluding predicting rapid spatial variation in hydraulic properties in association with bedform and instream roughness and flow obstruction variation. Accordingly, the designs are based on general, spatially averaged model predictions of velocity and shear stress, with an appropriate safety factor. Small scale variations in hydraulic properties should not be interpreted as signifying a meaningful feature of the design. Highly detailed design modeling of large wood structures is therefore not warranted, where structure stability and scour can be designed sufficiently using simply water depth and average channel values of velocity predicted by the model and increasing roughness locally.

In addition, the topographic extent of the area surveyed in some cases did not extend beyond the model predictions of inundation extent for the most extreme flood events, where the flooding extended onto the adjoining surface generated from the LiDAR data. As seen in Figure 14, the LiDAR data appear to be biased high along the stream channel. This results in artificially concentrating flood flows onto the area within the bounds of the survey, and thus potentially over-predicting water surface elevations

The use of a steady peak inflow rate is an appropriate assumption to meet design objectives at this site. Using a steady peak inflow rate provides a conservative estimate of inundation extents and water surface elevation (WSEL) associated with a given peak flow, which is used to determine the structure size and low chord, and loose LWM stability. Similarly, the model predictions of peak velocity are used to design general channel morphology, streambed composition, and both loose and fixed LWM stability. Each scenario is run for a sufficient time to fill storage areas and for WSELs to stabilize until flow upstream equals flow downstream. This modeling method does not account for the attenuation of peak flows between the actual upstream and downstream hydrographs, in particular with a large amount of storage upstream of the existing undersized culvert. During an actual runoff event, it is unlikely that the area upstream of the culvert would fill up entirely. An unsteady simulation could be used to route a hydrograph through the model to estimate peak flow attenuation for existing and proposed conditions. During an unsteady simulation, the areas upstream of the existing culvert would act as storage and, as a result, the flow downstream of the crossing would likely be less than the current design peak flow event. This is expected to be less of an issue for the natural conditions and proposed PHD scenarios at this site, however, where the channel size is small relative to the hydraulic opening, and the channel slope too steep, for flow attenuation effects to be significant.

The SRH-2D model outputs an estimate of shear stress that is calculated using a 2-D vector adaptation of the 1-D uniform flow approximation based on depth and energy slope. The program substitutes Manning's equation to calculate the slope, which results in shear stress estimate being proportional to the square of the Manning's n coefficient. Because Manning's n is used in the modeling as a surrogate for various energy losses in addition to grain friction, the resulting estimates of shear stress cannot be used to size streambed substrates or evaluate local scour depth. Values are presented in this report for

general reference, but should be treated generally as substantial over-estimates of the actual boundary shear stress (e.g., Pasternack et al. 2006). This is addressed directly in Section 5.1.

The model results and recommendations in this report are based on the conditions of the project site and the associated watershed at the time of this design. Any modifications to the site, man-made or natural, could alter the analysis, findings, and recommendations contained herein and could invalidate the analysis, findings, and recommendations. Site conditions, completion of upstream or downstream projects, upstream or downstream land use changes, climate changes, vegetation changes, maintenance practice changes, or other factors may change over time. Additional analysis or updates may be required in the future as a result of these changes.

4.2 Existing-Conditions Model Results

Locations of the cross sections used to report results for the existing-conditions hydraulic model are shown in Figure 30. The stationing for each cross section is assigned using the existing alignment as shown in Figure 31. Throughout this report the cross sections are designated using the letters to allow for direct comparison between existing, natural, and proposed conditions at specific locations as the existing and proposed alignments vary.

The hydraulic model results presented at each cross section include WSEL, depth, velocity, and shear stress as shown in Tables 8 and 9. Most variables are average values for the main channel except depth as it is reported as the maximum. More detailed hydraulic model results are included in Appendix C. Results of the hydraulic model are also presented along the longitudinal profile for the existing conditions as shown in Figures 32 and 33. Representative cross-section profiles are shown in Figures 34 and 35. Figures 36 and 37 depict the spatial distribution of predicted velocities at the 100-year flood under both downstream boundary control scenarios.

Results from the coincident 2-year, 100-year, and 500-year simulations indicate that the West Fork Hoquiam River has considerable effect on the tailwater condition of the crossing due to the proximity of the outfall with the confluence of the West Fork Hoquiam River. The effect of the West Fork Hoquiam can be seen by the flat water surface profiles in Figure 32. For the tributary simulations, higher channel velocities are observed at the outfall, as would be expected without tailwater influence. Overtopping of the road is not predicted to occur in each simulation. However, the culvert is undersized. As a result, events above the 2-year event submerge the culvert inlet, resulting in backwater upstream of the culvert, characterized by a flat water surface profile and velocities between 1.0 and 1.4 ft/s immediately upstream of the existing culvert.




Figure 30: Locations of cross sections used for reporting results of existing conditions simulations




Figure 31: Longitudinal profile stationing for existing conditions

Table 8: Hydraulic results for existing conditions within main channel

Hydraulic parameter	Cross section (STA, name)	2-year coincident peaks	100-year coincident peaks	500-year coincident peaks	2-year tributary	100-year tributary	500-year tributary
Average WSEL (ft)	STA 50+19 (A)	174.9	176.4	176.8	173.3	173.7	173.9
	STA 50+63 (B)	NA	NA	NA	NA	NA	NA
	STA 51+08 (C)	175.4	178.7	180.2	175.1	177.2	178.4
	STA 51+64 (D)	175.5	178.7	180.2	175.3	177.3	178.4
	STA 52+07 (E)	176.4	178.8	180.2	176.4	177.7	178.5
	STA 52+38 (F)	177.0	178.8	180.2	177.0	177.9	178.6
Maximum water depth (ft)	STA 50+19 (A)	3.2	4.7	5.1	1.5	2.0	2.2
	STA 50+63 (B)	NA	NA	NA	NA	NA	NA
	STA 51+08 (C)	2.9	6.2	7.7	2.6	4.8	5.9
	STA 51+64 (D)	1.8	5.1	6.6	1.7	3.7	4.8
	STA 52+07 (E)	2.3	4.7	6.2	2.3	3.6	4.5
	STA 52+38 (F)	1.5	3.3	4.7	1.5	2.4	3.1
Average velocity magnitude (ft/s)	STA 50+19 (A)	1.4	2.6	2.9	3.0	3.6	3.9
	STA 50+63 (B)	NA	NA	NA	NA	NA	NA
	STA 51+08 (C)	1.0	1.1	1.1	1.1	1.4	1.4
	STA 51+64 (D)	2.8	0.8	0.4	3.5	1.8	1.1
	STA 52+07 (E)	1.1	0.9	0.6	1.2	1.6	1.3
	STA 52+38 (F)	3.5	2.0	1.2	3.5	4.0	2.8
Average shear stress (lb/SF)	STA 50+19 (A)	0.3	0.7	0.9	1.8	2.6	2.9
	STA 50+63 (B)	NA	NA	NA	NA	NA	NA
	STA 51+08 (C)	0.2	0.2	0.2	0.3	0.3	0.3
	STA 51+64 (D)	1.4	0.1	0.0	2.1	0.4	0.2
	STA 52+07 (E)	0.2	0.1	0.0	0.2	0.3	0.2
	STA 52+38 (F)	2.1	0.5	0.1	2.1	2.1	1.0

ft/s = feet per second.

lb/SF = pounds per square foot.

Table 9: Existing-conditions velocities at select cross sections for 100-year tributary simulation

Location	100-year tributary average velocities (ft/s)		
	LOB ^a	Main ch.	ROB ^a
STA 50+19 (A)	0.02	3.56	1.06
STA 50+63 (B)	NA	NA	NA
STA 51+08 (C)	0.92	1.37	0.33
STA 51+64 (D)	0.37	1.83	0.32
STA 52+07 (E)	1.38	1.56	0.17
STA 52+38 (F)	1.98	3.96	1.1
a. Right overbank (ROB)/left overbank (LOB) locations determined from the top of bank. ft/s = feet per second.			




Figure 32: Existing-conditions water surface profiles, coincident peaks




Figure 33: Existing-conditions water surface profiles, tributary only




Figure 34: Typical upstream existing channel cross section (facing downstream), coincident peaks




Figure 35: Typical upstream existing channel cross section (facing downstream), tributary only




Figure 36: Existing-conditions present day 100-year velocity map (coincident peaks scenario)



Figure 37: Existing-conditions present day 100-year velocity map (tributary only scenario)

4.3 Natural-Conditions Model Results

Locations of the cross sections used to report results for the existing-conditions hydraulic model are shown in Figure 38. The existing culvert and alignment contain sharp bends in the stream and high gradients, creating high-velocity profiles. The natural conditions simulations use a modified alignment that reduces sharp channel bends at the structure and better matches the direction of overbank contours. This alignment is intended to match the tributary's natural condition prior to development. For the natural-conditions model, the roadway embankment and culvert were removed to approximate a floodplain at the location of the existing crossing.

The hydraulic model results presented at each cross section include WSEL, depth, velocity, and shear stress as summarized in Tables 10 and 11. Most variables are average values along the channel except the depth as it is reported as the maximum. More detailed hydraulic model results are included in Appendix C. Predicted WSELs are presented along the longitudinal profile for the proposed conditions as shown in Figures 39 and 40. Representative cross-section profiles are shown in Figures 41-44 for peak flows. Figures 45 and 46 depict the spatial distribution of predicted velocities at the 100-year flood under both downstream boundary control scenarios.

The natural coincident scenarios also indicate the crossing is heavily influenced by flows on the West Fork Hoquiam River. The tributary simulations demonstrate that a without tailwater influence, the channel is somewhat confined. Channel velocities in range from 2 to 5 ft/s. The velocity and shear distribution within the crossing is fairly even, lacking regions of high shear stress or velocity.




Figure 38: Locations of cross sections used for reporting results of natural conditions simulations

Table 10: Hydraulic results for natural conditions within main channel

Hydraulic parameter	Cross section (STA, name)	2-year coincident peaks	100-year coincident peaks	500-year coincident peaks	2-year tributary	100-year tributary	500-year tributary
Average WSEL (ft)	STA 0+18 (A)	175.0	176.5	176.9	173.3	173.9	174.1
	STA 0+61 (B)	175.0	176.5	176.9	174.2	174.9	175.0
	STA 1+00 (C)	175.1	176.5	177.0	174.8	175.5	175.6
	STA 1+42 (D)	175.5	176.6	177.0	175.4	176.1	176.3
	STA 1+85 (E)	176.2	177.3	177.7	176.2	177.2	177.5
	STA 2+15 (F)	177.0	177.8	178.1	177.0	177.8	178.0
Maximum water depth (ft)	STA 0+18 (A)	3.2	4.7	5.1	1.5	2.1	2.3
	STA 0+61 (B)	2.6	4.0	4.4	1.7	2.4	2.6
	STA 1+00 (C)	2.1	3.5	3.9	1.7	2.4	2.6
	STA 1+42 (D)	1.8	2.9	3.3	1.7	2.4	2.6
	STA 1+85 (E)	2.1	3.3	3.6	2.1	3.2	3.5
	STA 2+15 (F)	1.5	2.3	2.5	1.5	2.3	2.5
Average velocity magnitude (ft/s)	STA 0+18 (A)	0.8	1.2	1.2	2.6	3.6	3.7
	STA 0+61 (B)	1.0	0.9	0.9	2.1	3.0	3.1
	STA 1+00 (C)	1.5	1.1	1.0	2.2	2.8	2.9
	STA 1+42 (D)	2.1	2.0	2.0	2.2	3.0	3.2
	STA 1+85 (E)	1.5	2.2	2.3	1.5	2.3	2.4
	STA 2+15 (F)	3.4	4.1	4.1	3.4	4.1	4.3
Average shear stress (lb/SF)	STA 0+18 (A)	0.1	0.2	0.2	1.5	2.3	2.4
	STA 0+61 (B)	0.2	0.1	0.1	0.9	1.5	1.6
	STA 1+00 (C)	0.4	0.2	0.2	1.0	1.3	1.4
	STA 1+42 (D)	0.9	0.7	0.6	1.0	1.5	1.7
	STA 1+85 (E)	0.4	0.7	0.7	0.4	0.8	0.9
	STA 2+15 (F)	2.3	2.8	2.8	2.3	2.9	2.9

ft/s = feet per second.

lb/SF = pounds per square foot.

Table 11: Natural-conditions average velocities predicted for 100-year flood over floodplains and in main channel at select cross sections

Location	Coincident Peaks			Tributary Only		
	100-year Average Velocities (ft/s)			100-year Average Velocities (ft/s)		
	LOB ^a	Main ch.	ROB ^a	LOB ^a	Main ch.	ROB ^a
STA 0+18 (A)	2.5	1.2	0.5	0.5	3.6	0.6
STA 0+61 (B)	0.5	0.9	0.5	1.2	3.0	1.1
STA 1+00 (C)	0.6	1.1	0.5	1.3	2.8	1.1
STA 1+42 (D)	0.5	2.0	0.7	0.9	3.0	1.1
STA 1+85 (E)	1.4	2.2	0.5	1.3	2.3	0.6
STA 2+15 (F)	1.9	4.1	1.1	1.9	4.1	1.1

a. Right overbank (ROB)/left overbank (LOB) locations determined from top of bank.




Figure 39: Natural-conditions water surface profiles, coincident peaks




Figure 40: Natural-conditions water surface profiles, tributary only




Figure 41: Typical upstream natural channel cross section (facing downstream), coincident peaks




Figure 42: Typical upstream natural channel cross section (facing downstream), tributary only




Figure 43: Typical upstream natural channel cross section (facing downstream), coincident peaks




Figure 44: Typical upstream natural channel cross section (facing downstream), tributary only




Figure 45: Natural-conditions predicted velocity map with cross-section locations for present day 100-year coincident peaks simulation




Figure 46: Natural-conditions predicted velocity map with cross-section locations for the present day 100-year tributary simulation

4.4 Proposed Channel Design

This section describes the development of the proposed channel cross-section and layout design.

4.4.1 *Floodplain Utilization Ratio*

The floodplain utilization ratio (FUR) is determined by dividing the flood-prone width (FPW) by the BFW. A ratio under 3.0 is considered a confined channel, and above 3.0 is an unconfined channel. The FPW was determined from the modeled natural conditions 100-year tributary event at four cross sections upstream of the crossing. The FPW values were each divided by the design BFW of 9.0 feet to compute the FUR. Table 12 shows each FPW, the calculated FUR, and the average FUR across all cross sections. The average results in a FUR of 2.9; therefore, the channel is confined and a stream simulation design was accordingly developed for this site, which is predicated on emulating reference reach conditions.

It should be noted that the channel downstream of the culvert under backwater control from the West Fork Hoquiam River is unconfined, with floodplain flow controlled by the mainstem.

Table 12: FUR determination

Station	FPW (ft)	FUR
STA 0+61 (B)	26	2.9
STA 1+00 (C)	32	3.5
STA 1+42 (D)	28	3.1
STA 1+85 (E)	20	2.2
	Average	2.9

4.4.2 *Channel Planform and Shape*

The WCDG prefers in a stream simulation design that the channel planform and cross-section shape mimic conditions within a reference reach (Barnard et al. 2013). The proposed channel cross-section shape accordingly emulates WSDOT's typical reference channel-based design (Figure 47), with the relative location of the thalweg across the section varying depending on whether the channel is straight or curving. A meandering planform is proposed within the replacement structure to increase total roughness within the culvert and accordingly reduce velocities, and to provide greater habitat complexity.

The bottom cross-section shape of the reference-based channel has a bottom side slope of 5 horizontal (H):1 vertical (V) between the thalweg and bank toes, 2H:1V streambank slopes, and an overbank terrace at roughly a 15H:1V slope to create a channel similar to the observed existing channel shape. It is expected that the bottom shape will continue to adjust naturally during high water, where the proposed shape provides a reasonable starting point for subsequent channel shape evolution and bank stability will be provided via bioengineering design. Overall, the proposed design cross-section shape approximates reference reach conditions (Figure 48).




Figure 47: Reference channel-based design cross section for outside the culvert footprint




Figure 48: Comparison of design cross-section with a representative cross-section outside of the replacement structure footprint

Bioengineering methods can be implemented towards long term stability of the channel cross-section shape and planform outside the culvert. This is not necessarily the case for under replacement structures that are not long, high bridges, however, as is the case for this site where bank stabilizing vegetation typically will not grow and use of large woody material presents special constructability and maintenance problems. Except for very slow, low gradient channels, it is not possible to preserve a steep side slope without vegetation or specifying a particle size that is markedly larger than that typically specified for an alluvial, mobile streambed and is stable under all flows. For the project stream's gradient, side slope stability equations predict that gravel and cobble substrates will mobilize readily unless the cross-section is relatively flat (see Appendix D). Indeed, this is a primary reason why the profiles of constructed stream simulation designs using gravel and cobble tend to wash out and flatten within the first winter season of high flows. In the case of the project stream, calculations based on the hydraulic model predictions of shear stress and velocity during the 100-year flood peak indicate that

even a flat bottom cross-section is not stable when the streambed grain size distribution approximates the sieve sample in Table 4 (see Section 5).

However, the stream simulation design methodology as stipulated in WAC 220-660-190 is based on emulating a mobile bed reference channel morphology and substrate within the structure as well as outside, irrespective of future evolution of the channel cross-section profile. Given that vegetative stabilization is not feasible for this site, and measures to fix the bed in place are inconsistent with the stream simulation design approach, an alternate method is needed to counter flattening of the bed and preserve a meander morphology. Accordingly, the proposed design consists of a cobble surface armor layer placed on top of each meander bar. The cobble is sized to become partially mobile around the 100-year flood level so that material can adjust as needed yet remain within the culvert with the goal of preserving a meandering planform. The design rationale for specifying the grain size distribution of the cobble armor layer is described in greater detail Section 5. In general, the following considerations influenced design of the meander bars:

- The meander bars should be composed of a surface layer consisting of coarser cobble material that can self-organize into a stable, natural arrangement under a 100-year flood flow to avoid flattening out of the cross-section profile. Specific criteria include:
 - The grain size distribution of the material should reflect a critical dimensionless shear stress between 0.03 and 0.06, and closer to 0.03 in order to maintain a riffle form (e.g., Pasternack and Brown 2013; see Section 5.1).
 - The thickness of the surface layer should be at least twice the D_{90} of the cobble material, which is the general expected disturbance depth of a coarse bedded surface layer that is disturbed by mobilizing flows (cf. Wilcock et al. 1996; DeVries 2002). It is not necessary to extend this material all the way down to the bottom of the streambed fill because it is designed to adjust with streambed regrading but generally remain at the same location within the culvert. However, in cases where an additional safety factor is desired, the layer can extend down to the depth of the constructed thalweg.
- The design goal for spacing of the bars should reflect a maximum head drop over a naturally formed riffle, rather than emulating a classic geomorphic pool-riffle spacing criterion, given the meander bars are intended to be effectively stable. To reduce the potential for re-grading to adversely affect upstream swimming ability, the head drop between bar centerlines (across the channel) should be below typical criteria for juvenile salmonids to accommodate upstream movements of other native fish species. For this site, a head drop of 3 inches between bar apices was selected based on professional judgment, where the drop is expected to be across a naturally formed riffle after the streambed is reworked by floods, assuming worst case regrading occurs such that the gradient of the streambed between bar apices becomes flatter.
- The bar material should not protrude above the design surface, where the intervening material is designed to be in flush with the edge of the bar material and is sized to be stable on the prevailing stream gradient and side slope.
- Additionally, stable habitat boulders (typically 2-man or larger; WSDOT specification 9-03.11(4)) can be placed embedded into the streambed surface to increase channel roughness, which helps slow velocities within the structure and provide hydraulic sheltering for fish during high flows.

The corresponding proposed design is depicted schematically in Figure 49.




Figure 49: Schematic of proposed channel planform (top) and cross-section (bottom) layout inside the culvert. If there is concern of future loss of bar material to downstream, the thickness of the cobble layer can be increased to the dashed line

4.4.3 Channel Alignment

The proposed project stream alignment deviates from the existing alignment to result in requiring a shorter culvert. Because the existing alignment has several sharp meanders in the vicinity of the culvert inlet, the proposed alignment was modified to result in bends with reduced radii of curvature, which can reduce erosion risk. The new alignment was determined by removing the channelized reach downstream of the existing culvert, meeting slope ratio requirements, and limiting impacts to the existing stream. Length of grading was based on meeting the slope ratio and limited grading extents,

and tie-in points were chosen at locations that tie in with the existing upstream and downstream grade. The proposed channel alignment and grading extents are illustrated in design drawings provided in Appendix E.

4.4.4 Channel Gradient

The WCDG recommends that the proposed culvert bed gradient not be more than 25 percent steeper than the existing stream gradient upstream of the crossing (WCDG Equation 3.1). The proposed channel is graded between approximately 9 feet downstream of the culvert outlet and 50 feet upstream of the culvert inlet, with a gradient of approximately 1.5 percent, intermediate to the steeper upstream gradient in the project stream and the lower downstream gradient of the West Fork Hoquiam River. The alignment and grading extents are illustrated in design drawings provided in Appendix E. The proposed channel gradient is approximately 83 percent of the average reference reach gradient of 1.8 percent upstream. This slope ratio is under the WCDG's recommended maximum value of 1.25 (Barnard et al. 2013).

4.5 Design Methodology

The proposed culvert hydraulic design was developed using the 2013 *Water Crossing Design Guidelines* (Barnard et al. 2013) and the WSDOT *Hydraulics Manual* (WSDOT 2019). Using the guidance in these two documents, the stream simulation design method was determined to be the most appropriate at this crossing because the channel is confined upstream with a calculated FUR less than 3.0, the BFW was determined to be less than 15 feet, the slope ratio is less than 1.25, and there is limited concern for lateral migration.

4.6 Future Conditions: Proposed 13-Foot Minimum Hydraulic Opening

The determination of the proposed minimum hydraulic opening width is described in section 4.7. A 13-foot opening was modeled as an open channel with 9 ft BFW channel and floodplain, with vertical side walls. The channel bankfull cross-section profile matched the shape in Figure 47 both inside and outside the culvert. The resulting hydraulic predictions were used in the analyses to yield conservative design parameters for freeboard and substrate sizing. Locations of the cross sections used to report results for the proposed-conditions hydraulic model are shown in Figure 50. The stationing for each cross section is assigned using the proposed alignment as shown in Figure 51.

The hydraulic model results presented at each cross section include WSEL, depth, velocity, and shear stress as shown in Tables 13 and 14. Most variables are average values along the channel except for the depth as it is reported as a maximum. More detailed hydraulic model results are included in Appendix C. Predicted WSELs are presented along the longitudinal profile for the proposed conditions as shown in Figures 52 and 53. Representative cross-section profiles are shown in Figures 54-57 for the 100-year flood in the channel upstream and in the replacement culvert. Figures 58-61 depict the spatial distribution of velocities during the present day and anticipated future 100-year flood peaks from both downstream boundary condition scenarios.

Based on the tributary and coincident scenarios for the 2-year, 100-year, and 500-year events, there is significantly less backwater upstream of the crossing in the existing conditions simulations compared

with the proposed minimum hydraulic opening. In the 100-year tributary simulation, very little hydraulic constriction is observed, and the structure has little impact on the water surface profile. Because the flow is less constricted and channel widths upstream, downstream, and through the structure are relatively consistent, similar to the natural conditions simulation.




Figure 50: Locations of cross sections used for reporting results of proposed PHD simulations




Figure 51: Longitudinal profile stationing for proposed conditions

Table 13: Average main channel hydraulic results for proposed conditions upstream and downstream of structure
(C=coincident peaks, T=tributary only)

Hydraulic parameter	Cross section Sta	2-year (C)	100-year (C)	2080 100-year (C)	500-year (C)	2-year (T)	100-year (T)	2080 100-year (T)	500-year (T)
Average WSEL (ft)	0+18 (A)	174.9	176.3	176.4	176.6	173.3	173.9	173.9	174.0
	0+61 (B)*	174.9	176.3	176.4	176.6	173.8	174.4	174.5	174.6
	1+00 (C)	175.0	176.3	176.5	176.7	174.5	175.2	175.3	175.4
	1+42 (D)	175.4	176.5	176.6	176.8	175.4	176.0	176.1	176.2
	1+85 (E)	176.1	177.2	177.3	177.6	176.1	177.2	177.3	177.5
	2+15 (F)	177.0	177.8	177.8	178.0	177.0	177.7	177.8	177.9
Maximum water depth (ft)	0+18 (A)	3.1	4.5	4.6	4.8	1.5	2.0	2.1	2.2
	0+61 (B)*	2.5	3.8	4.0	4.2	1.3	2.0	2.0	2.1
	1+00 (C)	1.9	3.3	3.4	3.6	1.4	2.1	2.2	2.3
	1+42 (D)	1.7	2.8	2.9	3.1	1.6	2.3	2.4	2.5
	1+85 (E)	2.1	3.2	3.3	3.5	2.1	3.1	3.2	3.4
	2+15 (F)	1.5	2.2	2.3	2.4	1.5	2.2	2.3	2.4
Average velocity magnitude (ft/s)	0+18 (A)	0.8	1.3	1.4	1.4	2.7	3.9	3.9	4.0
	0+61 (B)*	1.2	1.6	1.7	1.8	3.0	4.6	4.7	4.9
	1+00 (C)	1.9	1.9	2.0	2.0	2.8	3.9	4.0	4.1
	1+42 (D)	2.3	2.3	2.3	2.3	2.4	3.3	3.4	3.5
	1+85 (E)	1.6	2.4	2.4	2.5	1.6	2.4	2.5	2.6
	2+15 (F)	3.5	4.4	4.5	4.5	3.5	4.4	4.5	4.6
Average shear stress (lb/SF)	0+18 (A)	0.1	0.2	0.2	0.2	1.4	2.2	2.2	2.3
	0+61 (B)*	0.1	0.1	0.1	0.1	0.6	0.9	1.0	1.1
	1+00 (C)	0.5	0.4	0.5	0.5	1.5	2.2	2.2	2.3
	1+42 (D)	0.8	0.7	0.7	0.7	0.9	1.5	1.5	1.6
	1+85 (E)	0.4	0.7	0.7	0.7	0.4	0.7	0.8	0.8
	2+15 (F)	2.1	2.6	2.7	2.7	2.1	2.7	2.7	2.7

* - at structure

Table 14: Proposed-conditions average velocities predicted for 100-year flood over floodplains and in main channel at select cross sections

Location	Coincident Peaks			Tributary Only		
	100-year Average Velocities (ft/s)			100-year Average Velocities (ft/s)		
	LOB ^a	Main ch.	ROB ^a	LOB ^a	Main ch.	ROB ^a
STA 0+18 (A)	2.9	1.3	0.5	0.4	3.9	0.6
STA 0+61 (B)	1.6	1.6	1.3	2.3	4.6	2.5
STA 1+00 (C)	0.6	1.9	0.5	1.7	3.9	1.0
STA 1+42 (D)	0.5	2.3	0.8	0.9	3.3	1.1
STA 1+85 (E)	1.4	2.4	0.5	1.4	2.4	0.5
STA 2+15 (F)	2.0	4.4	1.1	2.0	4.4	1.1
b. Right overbank (ROB)/left overbank (LOB) locations determined from the top of the bank						




Figure 52: Proposed-conditions water surface profiles, coincident peaks




Figure 53: Proposed-conditions water surface profiles, tributary only




Figure 54: Typical section upstream of proposed structure (facing downstream), coincident peaks




Figure 55: Typical section upstream of proposed structure (facing downstream), tributary only




Figure 56: Typical section within proposed structure (facing downstream), coincident peaks




Figure 57: Typical section within proposed structure (facing downstream), tributary only




Figure 58: Proposed-conditions predicted 100-year velocity map for coincident peaks scenario




Figure 59: Proposed-conditions predicted 2080 100-year velocity map for coincident peaks scenario




Figure 60: Proposed-conditions predicted 100-year velocity map for tributary only scenario




Figure 61: Proposed-conditions predicted 2080 100-year velocity map for tributary only scenario

4.7 Water Crossing Design

Water crossing design parameters includes structure type, minimum hydraulic opening width and length, and freeboard requirements.

4.7.1 *Structure Type*

A concrete box culvert is under consideration presently for this site.

4.7.2 *Minimum Hydraulic Opening Width and Length*

The hydraulic opening is defined as the width perpendicular to the creek beneath the proposed structure that is necessary to convey the design flow and allow for natural geomorphic processes. The hydraulic opening assumes vertical walls at the edge of the minimum hydraulic opening width unless otherwise specified. The starting point for the design of WSDOT structures is Equation 3.2 of the WCDG (Barnard et al. 2013), rounded up to the nearest whole foot. For this crossing, a minimum hydraulic opening of 13 feet was determined to be the minimum starting point. This value was based on a design BFW of 9.0 feet per concurrence of the co-managers and the Stream Team.

The present day 100-year and projected 2080 100-year flood magnitudes were simulated for the proposed conditions to evaluate predicted velocities within a 13 feet wide structure. Initial calculations performed during development of the draft PHD were based on assuming a similar roughness inside the replacement structure as in the natural channel, which resulted in predicting velocities that may be lower than would actually occur. As discussed in Section 4.4.2, the roughness in the project stream should not be expected to be similar inside the culvert as outside. As a consequence, the calculated velocity will be higher than when assuming similar roughness values throughout, irrespective of hydraulic opening width. Updated main channel velocity predictions are summarized for both the tributary only and coincident peaks scenarios in Table 15. The tributary only scenario is associated with velocities that are relatively high, whereas the coincident peaks scenario is associated with relatively low velocities at the 100 year flood peak. However, neither scenario is likely. It is more likely that the West Fork Hoquiam River would be at an intermediate flood level when the project stream experiences a 100-year flood, and so a separate model run was performed assuming a concurrent 10-year flood in the mainstem. The resulting velocity prediction is comparable to the coincident peaks scenario, and the magnitude of the velocity within the 13 feet wide structure is less than predicted in the natural channel upstream (Table 15; cf. Appendix C). The magnitude is also less than that estimated to be required to scour out the native gravel grain size distribution (cf. Isbash mobility relation in USACE 1994, Table 4).

A separate check was performed to evaluate if widening the structure would reduce the tributary only velocity predictions, where an opening of 18 feet was also simulated. Predicted water surface elevations were similar for the two widths (Figure 62), with corresponding similar velocities. This indicates that a wider structure opening would not bring the velocity down significantly for the tributary only scenario. Consequently, a 13 feet wide hydraulic opening was considered sufficient for this site.

The proposed structure (Appendix E) is approximately 53 feet in length, which is within the WCDG's maximum length:width ratio criterion of 10 for a stream simulation design. The ultimate length will be confirmed at a later stage of design.

Table 15: Predicted main channel velocities within 13 feet and 18 feet wide structures

Simulation	Velocity in 13 Feet Wide Structure (ft/s)	Velocity in 18 Feet Wide Structure (ft/s)
Tributary Only: 100-year	4.6	4.6
Tributary Only: 2080 100-year	4.7	4.7
Coincident Peaks: 100-year	1.6	1.3
Coincident Peaks: 2080 100-year	1.7	1.4
Tributary 100-year, W Fk Hoquiam 10-Year	1.9	Not simulated




Figure 62: Proposed-conditions predicted 100-year water surface elevations for 13 feet and 18 feet wide structures, tributary only scenario

4.7.3 Freeboard

Freeboard is necessary to allow the free passage of debris expected to be encountered. The WCDG generally suggests a minimum 2-feet clearance above the 100-year WSEL for streams with a BFW of between 8-15 feet to adequately pass debris (Barnard et al. 2013). WSDOT also desires a minimum vertical clearance between the culvert soffit and the streambed thalweg for maintenance equal to 6 feet. WSDOT is incorporating climate resilience in freeboard, where practicable, and so freeboard was evaluated at both the 100-year WSEL and the projected 2080 100-year WSEL. The hydraulic modeling indicates that the maintenance-based goal will exceed the clearance required to meet the 2 feet hydraulic-based criterion associated with the proposed design when constructed.

The evaluation of long-term aggradation and degradation presented in Section 2.8.4 indicated that there is a low likelihood of aggradation at the site, but that if it did occur, it would likely be around 1 foot or less. This can be added to the minimum required freeboard (Table 16).

Table 16: Parameters relevant to freeboard specification for proposed 13 feet wide replacement structure

Parameter	2080 100-Year Coincident Flood Predictions	
	At Inlet	At Outlet
Thalweg elevation (ft)	173.0	172.1
Maximum WSEL (ft)	175.2	174.4
Minimum low chord elevation to provide 2 feet of freeboard (ft)	177.2	176.4
Minimum low chord elevation to provide 6 feet maintenance access (ft)	179.0	178.1
Minimum low chord elevation to provide 2 feet of freeboard, without future aggradation (ft)	178.2	177.4
Recommended low chord elevation, with future aggradation (ft)	179.0	178.1

4.7.3.1 Past Maintenance Records

No maintenance problems related to flooding have been recorded by WSDOT for this crossing.

4.7.3.2 Wood and Sediment Supply

The contributing basin is predominantly forested with large trees present that are a potential source of LWM. Based upon the flow velocities, depths of flow, and BFW of the stream, the potential to transport LWM is low. Further, the overbanks are well vegetated and forested, which further impedes the ability to transport LWM. As described in section 2.8.6, mobile wood pieces in the stream appear to be smaller than 6 inches in diameter and around 7 feet in length, and thus would be expected to clear easily under the proposed 13 feet wide structure with 2 feet of freeboard during the 100-year flood.

4.7.3.3 Flooding

As described in Section 2.3, the site is not located in a FEMA-delineated floodplain. Historical flooding problems have not been noted by WSDOT for this site. The proposed hydraulic opening will increase the capacity of the crossing and significantly reduce the backwater in comparison to the existing conditions.

4.7.3.4 Future Corridor Plans

There are currently no long-term plans to improve U.S. 101 through this corridor.

4.7.3.5 Impacts

It is not anticipated that the road level will be raised to accommodate the proposed minimum hydraulic opening. A final decision will be made at a later design phase.

4.7.3.6 Impacts to Fish Life and Habitat

It is expected that the proposed freeboard of 2 feet will result in no substantial impacts to fish life and habitat.

5 Streambed Design

The streambed design considered the local characteristic grain size distribution (GSD) of gravel collected in the sieve sample, standard streambed stability calculations for the proposed channel longitudinal and cross-section profile grading, and requirements of WAC 220-160-190. Two GSDs will be proposed for this site. One grain size distribution is for the streambed mix, which is presented in the section below, and the second is for proposed meander bars within the replacement structure. Partial channel-spanning meander bars are recommended within the proposed structure to encourage natural channel evolution and flow complexity within the constructed channel. The gradation for the proposed meander bars will be designed during the FHD phase. In addition, large woody material is proposed to be placed on and over the streambed to provide instream habitat complexity and overhead cover for fish. These two elements of the design are described in separate sections below.

5.1 Bed Material

Where neither of the other two alternative approaches identified in Section 1.0 are indicated for implementation, the injunction requires that the design follow the stream simulation methodology as described in the WAC and WCDG (Barnard et al. 2013). WAC 220-660-190 stipulates that “The median particle size of sediment placed inside the stream-simulation culvert must be approximately twenty percent of the median particle size found in a reference reach of the same stream. The department [WDFW] may approve exceptions if the proposed alternative sediment is appropriate for the circumstances.”

For sediment sizing, WSDOT uses the Modified Critical Shear Stress Approach, as described in Appendix E of the 2008 US Forest Service (USFS) Guidelines for all systems under 4 percent and the Unit-Discharge Bed Design as described by the 2013 WCDG for systems greater than 4 percent. Since the grade of the unnamed tributary to Stevens Creek near the US 101 crossing is less than 4 percent, the proposed streambed gradation for the new channel was sized using the Modified Shield’s Critical Shear Stress Approach. The mobility analysis performed on the design gradation detailed below uses the 100-year peak flow as the design flow.

The reference reach of this stream is primarily composed of fines, with some isolated gravel patches. A sieve sample was taken during the June 2021 site visit to characterize one of the isolated gravel patches. The findings of this sieve sample are discussed in Section 2.8.3. The proposed streambed mix is designed to be more consistent with the fine sediments and gravelly material found in the reference reach while conforming to the standards put forth by the WAC. The proposed gradation for the unnamed tributary to the West Fork Hoquiam River is 80 percent of Section 9-03.11(1) Streambed Sediment and 20 percent of Section 9-03.11(2) 4-inch Streambed Cobbles. Calculations based on the Modified Shields stress method indicate that every particle size will remain immobile during the 2-year storm event and will be mobile during the 100-year event, thus providing stability within the stream during the low flow events while providing continuity of sediment transport during the higher flow events. Thus, there is a risk that the streambed will regrade without the presence of coarser meander bars. A summary of the observed and proposed overall streambed gradations is presented in Table 17, where the proposed GSD reflects

the stable D_{84} size and using WSDOT's standard specification 9-03.11(1). WSDOT's worksheet calculations for the proposed streambed mix are presented in Appendix D. As previously mentioned, the proposed meander bar gradation will be coarser and will be included with the final hydraulic design.

Table 17: Comparison of observed and stable streambed, and proposed stream simulation and meander bar material grain size distributions

	Observed Diameter (in)	Proposed Diameter (in)
D₁₆	0.1	0.1
D₅₀	1.0	0.8
D₈₄	1.9	2.0
D₉₀	2.1	2.3
D_{max}	3.5	3.5

5.2 Channel Complexity

To mimic the natural riverine environment and promote the formation of habitat, the design incorporated placement of key LWM pieces within and across the channel and floodplain. Placement will generally mimic tree fall that is common throughout the reach upstream of the crossing, and embedded wood pieces in the reach downstream to reflect characteristic geomorphic processes in the West Fork Hoquiam River. Complexity is also provided by the meander bar layout proposed in Section 4.4.

5.2.1 Design Concept

The total number of key pieces was determined in consideration of criteria presented in Fox and Bolton (2007) and Chapter 10 of the *Hydraulics Manual* (WSDOT 2019), in which WSDOT's recommended key piece density for the project site is 3.4 key pieces and 39.48 cubic yards of volume per 100 feet of channel. A key piece is defined as having a minimum volume of 1.31 cubic yards, which corresponds roughly to a 30 feet long log that has a diameter at breast height (DBH) of 15 inches. WSDOT has established a design goal for this project where the Fox and Bolton (2007) criteria are to be calculated for the total regrade reach length including the culvert, but the pieces of wood are to distribute outside of the culvert. For the proposed total regrade length of 145 feet, the design criteria for this reach are five key pieces with a total volume of 57.2 cubic yards (Appendix H). In small streams, the volume criterion may not always be practically achieved without completely filling the channel and placing a sizeable amount of wood outside of the 2-year flood extent, where smaller diameter logs can achieve the same biological and geomorphic functions. In this design, the primary goal was to exceed the density criterion to get closer to or even meet the volume criterion, while not overloading the stream channel outside of the culvert. Where feasible, wood can be added outside of the regrade extent with the condition that heavy equipment not disturb the channel and floodplain significantly.

A conceptual LWM layout has been developed for the project reach involving a mix of embedded and loose logs with rootwads (Figure 63). The conceptual layout proposes 8 key pieces in a 145-foot-long project reach (including the structure length), which exceeds the number criterion. There is space for this number of pieces, and it allows for smaller pieces of wood in the 14- to 18-inch DBH range, sizes that are comparable to other pieces of wood at the site and gives the contractor flexibility in sourcing wood. This increased number of variable sized pieces in turn facilitates meeting the net volume target.

The mobility and stabilization of LWM will be analyzed in later phases of design. The design involves two log types:

- 3 embedded logs (Type 1) with rootwads to provide habitat and stabilize the constructed left streambank above and below the culvert; the logs downstream are intended to retard meander migration of the West Fork Hoquiam River left bank to reduce potential for incision in the tributary stream. The rootwad will be placed in the low flow channel with a preformed scour hole around it, and the butt end will be buried to sufficient length and depth that additional anchoring is not needed.
- 5 loose, 30+ feet long logs with rootwads, and to the extent possible, with intact branches. One will be placed entirely in the channel (Type 2), two will be placed with rootwad in the channel and tip on the floodplain/adjacent slope (Type 3), and two will span the bankfull channel to promote scouring underneath (Type 4). The type 3 and 4 designs will involve self-ballasting and interlocking with existing trees for stability. The type 2 log will be kept in place by other logs on top, and wedging between streambanks.

The LWM pieces will be placed so they provide habitat features for fish, form pools, and refuge habitat under high flow conditions. Wood stability and the need for anchoring will be assessed at the Final Hydraulic Design (FHD) level. Key pieces will be designed to be anchored by either suitable embedment length/depth, or interlocking with existing trees. To meet WSDOT's total LWM number target, nine (9) additional 12" or larger DBH trees with rootwads would be needed. These smaller pieces would need to be placed loose as directed work, or designed to be embedded in the banks, integrated with the installation of key pieces.

Risk of fish stranding during summer flow conditions is minimal because proposed grading directs flow back to the main channel and does not promote isolated pools. Similar to a natural stream system, there is the potential for floodplain pools that create some potential to isolate fish that have entered during high flow events.




Figure 63: Conceptual layout of key LWM and meander bars for habitat complexity

6 Floodplain Changes

This project is not within a mapped floodplain. The pre-project and expected post-project conditions were evaluated to determine whether there would be a change in WSEL and floodplain storage.

6.1 Floodplain Storage

Floodplain storage is anticipated to be affected by the proposed structure. The installation of a larger hydraulic opening greatly reduces the amount of backwater and associated peak flow attenuation that was being provided by the smaller, existing culvert. A comparison of pre- and post-project peak flow events was not quantified as the models were run with a steady flow rate specified at the upstream boundary of the model. There is no known existing infrastructure downstream of the crossing that would be potentially impacted, however.

6.2 Water Surface Elevations

Installation of the proposed structure would reduce the backwater impacts immediately upstream of the existing culvert, resulting in a reduction in WSEL. The WSEL is reduced by as much as 2 feet near the inlet of the existing culvert at the 100-year event as shown in Figures 64 and 65. Figure 66 shows a significant decrease in backwater with the proposed structure alignment, opening, and grading, during the coincident peak 100-Year condition.




Figure 64: Existing and proposed 100-year water surface profile comparison, tributary only




Figure 65: Existing and proposed 100-year water surface profile comparison, coincident peaks




Figure 66: Water surface elevation change from existing (top) to proposed (bottom) conditions

7 Climate Resilience

WSDOT recognizes climate resilience as a component of the integrity of its structures and approaches the design of bridges and buried structures through a risk-based assessment. For bridges and buried structures, the largest risk to the structures will come from increases in flow. The goal of fish passage projects is to maintain natural channel processes through the life of the structure and maintain passability for all expected life stages and species in a system. At a minimum, climate change is addressed in all bridge, buried structure, and fish passage projects by providing a design in which the foundations or bottoms are not exposed during the 500-year flow event due to long-term degradation or scour. WSDOT also completes a hydraulic model for all water crossings on fish-bearing streams, regardless of design methodology, to ensure that the new structure is appropriately sized. If the velocities through the structure differ greatly from those found elsewhere in the reach, the structure width may be increased above what is required by Equation 3.2 in the WCDG.

General climate change predictions for the broader region are for increased rainfall intensity during winter months, with the caveat that there is great spatial variability in the projections that may preclude downscaling to the project site drainage area, which is relatively small (WSDOT 2011). The project site crossing has been evaluated and determined to be a low risk site based on the Climate Impacts Vulnerability Assessment maps (Figure 67). Based on the determination of this location being a low risk site, no additional climate change design modifications were made. The new structures were designed so their foundations do not become exposed during the 500-year flow event. Also, hydraulic modeling indicated that the flow through the replacement culvert is not predicted to become pressurized (i.e., no freeboard) during the 500-year event.

7.1 Climate Resilience Tools

WSDOT also evaluates crossings using the mean percent change in 100-year flood flows from the WDFW Future Projections for Climate-Adapted Culvert Design program (Appendix I). All sites consider the 2080 percent increase throughout the design of the structure.

7.2 Hydrology

For each design WSDOT uses the best available science for assessing site hydrology. The predicted flows are analyzed in the hydraulic model and compared to field and survey indicators, maintenance history, and any other available information. Hydraulic engineering judgment is used to compare model results to system characteristics; if there is significant variation, then the hydrology is reevaluated to determine whether adjustments need to be made, including adding standard error to the regression equation, basin changes in size or use, etc.

In addition to using the best available science for current site hydrology, WSDOT is evaluating the structure at the 2080 predicted 100-year flow event to check for climate resilience. The design flow for the crossing is 58 cfs at the 100-year storm event. The projected increase for the 2080 flow rate is 9 percent, yielding a projected 2080 flow rate of 63 cfs. The design flow for the West Fork Hoquiam is 428

cfs at the 100-year storm event. The projected increase for the 2080 flows at the crossing were also applied to the West Fork Hoquiam River yielding a projected 2080 flow rate of 467 cfs.

7.3 Climate Resilience Summary

A minimum hydraulic opening of 13 feet and a minimum maintenance requirement clearance of 6 feet from the channel thalweg to the inside top of structure allows for extreme event flows to pass through the replacement structure safely under the projected 2080 100-year flow event. This will help to ensure that the structure is resilient to climate change and the system is allowed to function naturally, including the passage of sediment, debris, and water in the future.




Figure 67: Climate impacts vulnerability assessment of Olympic Region areas 3 and 4 (source: WSDOT 2011). Site location is indicated by star

8 Scour Analysis

Total scour will be computed during later phases of the project using the 100-year, 500-year, and projected 2080 100-year flow events. The structure will be designed to account for the potential scour at the projected 2080 100-year flow events. For this phase of the project, the risk for lateral migration and potential for degradation are evaluated on a conceptual level. This information is considered preliminary and is not to be taken as a final recommendation in either case.

8.1 Lateral Migration

Based on the evaluation in section 2.8.5, the risk for lateral migration of the project stream is considered negligible. However, given the crossing is located just upstream of the confluence with the West Fork Hoquiam River, there is some risk to the crossing and roadway from lateral migration of the mainstem channel. The risk is considered generally low based on the apparent stability of the mainstem planform in the vicinity of the confluence. Nonetheless, to counter potential channel migration and resulting lowering of the project stream grade downstream of the culvert, the design includes installation of embedded LWM along the left bank of the project stream below the culvert, in anticipation of future meander migration of the mainstem.

8.2 Long-term Aggradation/Degradation of the Riverbed

Based on the evaluation in section 2.8.4, there is a little risk of long-term aggradation at the project site over the life of the replacement structure. There is some risk of degradation if grade controls in the West Fork Hoquiam River decompose or wash out, where the 1.8 percent gradient in the long profile upstream extends downstream. The maximum degradation in that scenario would be less than 2 feet at the downstream end and 0.5 feet at the upstream end of the replacement culvert.

8.3 Local Scour

Three types of scour will be evaluated at this site: bend scour upstream near the inlet, inlet scour, and contraction scour. Initial scoping level calculations indicate the amount of local scour will likely be small, on the order of 1 feet. These forms of scour will be evaluated in greater depth after the stream channel design has been finalized. Large wood pieces placed in the channel will have pre-formed scour holes constructed prior to rootwad placement.

Summary

Table 18 presents a summary of this PHD Report results.

Table 18: Report summary

Stream crossing category	Elements	Values	Report location
Habitat gain	Total length	3,401'	2.4 Site Description
Bankfull width	Average BFW	9.0'	2.8.2 Channel Geometry
	Reference reach found?	Y	2.8.1 Reference Reach Selection
Channel slope/gradient	Existing crossing	1.7%	2.8.4 Vertical Channel Stability
	Reference reach	1.9%	2.8.1 Reference Reach Selection
	Proposed	1.5%	4.4.2 Channel Planform and Shape
Countersink	Proposed	FHD	4.7.3 Freeboard
	Added for climate resilience	FHD	4.7.3 Freeboard
Scour	Analysis	FHD	8 Scour Analysis
	Streambank protection/stabilization	FHD	8 Scour Analysis
Channel geometry	Existing	-	4.4.2 Channel Planform and Shape
	Proposed	Realign	4.4.2 Channel Planform and Shape
Floodplain continuity	FEMA mapped floodplain	N	6 Floodplain Changes
	Lateral migration	Low	2.8.5 Channel Migration
	Floodplain changes?	Y	6 Floodplain Changes
Freeboard	Proposed	2.0'	4.7.3 Freeboard
	Added for climate resilience	Incorporated	4.7.3 Freeboard
	Additional recommended	1.0'	4.7.3 Freeboard
Maintenance clearance	Proposed	6.0'	4.7.3 Freeboard
Substrate	Existing	D ₅₀ =1.0"	2.8.3 Sediment
	Proposed	D ₅₀ =0.8"	5.1 Bed Material
Hydraulic opening	Proposed	13.0'	4.7.2 Minimum Hydraulic Opening Width and Length
	Added for climate resilience	N	4.7.2 Minimum Hydraulic Opening Width and Length
Channel complexity	LWM	Y	5.2 Channel Complexity
	Meander bars	Y	4.4.2 Channel Planform and Shape
	Boulder clusters	MAYBE	4.4.2 Channel Planform and Shape

	Mobile wood	N	5.2 Channel Complexity
Crossing length	Existing	80'	2.7.2 Existing Conditions
	Proposed	53'	4.7.2 Minimum Hydraulic Opening Width and Length
Floodplain utilization ratio	Flood-prone width	26.5'	4.2 Existing-Conditions Model Results
	Average FUR upstream and downstream	2.9	4.2 Existing-Conditions Model Results
Hydrology/design flows	Existing	Regress	3 Hydrology and Peak Flow Estimates
	Climate resilience	Yes	3 Hydrology and Peak Flow Estimates
Channel morphology	Existing	Stage 1	2.8.5 Channel Migration
	Proposed	Stage 1	5.2 Channel Complexity
Channel degradation	Potential?	Low	8.2 Long-term Aggradation/Degradation of the Riverbed
	Allowed?	Y	8.2 Long-term Aggradation/Degradation of the Riverbed
Structure type	Recommendation	N	4.7.1 Structure Type
	Type	NA	4.7.1 Structure Type

References

Aquaveo. 2018. SMS Version 13.1.11.

Arcement, G.J. and V.R. Schneider, 1989. Guide for selecting Manning's roughness coefficients for natural channels and flood plains. U.S. Geological Service Water-Supply Paper 2339.

Barnard, R.J., J. Johnson, P. Brooks, K.M. Bates, B. Heiner, J.P. Klavas, D.C. Ponder, P.D. Smith, and P.D. Powers. 2013. *Water Crossing Design Guidelines*. Washington State Department of Fish and Wildlife. Olympia, Washington.

Barnes, H.H. 1967. Roughness characteristics of natural channels. U.S. Geological Service Water-Supply Paper 1849.

Chow, V.T. 1959. *Open Channel Hydraulics*, McGraw-Hill Book Company, New York.

DeVries, P. 2002. Bedload layer thickness and disturbance depth in gravel bed streams. *Journal of Hydraulic Engineering*, 128(11), pp.983-991.

DeVries, P., C. Huang, and R. Aldrich. 2014. Sediment Transport Modeling Along the Gravel-Sand Transition Zone of the Snohomish River, WA. In AGU Fall Meeting Abstracts (Vol. 2014, pp. EP53C-3675).

Fox, M. and S. Bolton. 2007. A Regional and Geomorphic Reference for Quantities and Volumes of Instream Wood in Unmanaged Forests Basins of Washington Stat. *North American Journal of Fisheries Management*. Vol 27, Issue 1. Pg. 342–359.

Lisle, T.E., J.M. Nelson, J. Pitlick, M.A. Madej, and B.L. Barkett. 2000. Variability of bed mobility in natural, gravel-bed channels and adjustments to sediment load at local and reach scales. *Water Resources Research*, 36(12), pp.3743-3755.

Logan, R.L. 2003. *Geologic Map of the Shelton 1:100,000 Quadrangle, Washington*. Washington State Department of Natural Resources

Mastin, M.C., C.P. Konrad, A.G. Veilleux, and A.E. Tecca. 2016, Magnitude, frequency, and trends of floods at gaged and ungaged sites in Washington, based on data through water year 2014 (ver 1.2, November 2017): U.S. Geological Survey Scientific Investigations Report 2016–5118, 70 p., <http://dx.doi.org/10.3133/sir20165118>.

Mooney, D.M., C.L. Holmquist-Johnson, and S. Broderick. 2007. *Rock ramp design guidelines*. Bureau of Reclamation.

National Land Cover Database (NLCD). 2016. <https://www.mrlc.gov/data/nlcd-2016-land-cover-conus> [June 01, 2020].

Pasternack, G.B., A.T. Gilbert, J.M. Wheaton, and E.M. Buckland. 2006. Error propagation for velocity and shear stress prediction using 2D models for environmental management. *Journal of Hydrology*, 328(1-2), pp.227-241.

Pasternack, G.B. and R.A. Brown. 2013. Ecohydraulic design of riffle-pool relief and morphological unit geometry in support of regulated gravel-bed river rehabilitation. DOI 10.1002/9781118526576.ch20

PRISM Climate Group. 2019. Oregon State University, <http://prism.oregonstate.edu>, created February 4, 2004.

Rapp, C. and T.B. Abbe. 2003. A Framework for Delineating Channel Migration Zones (#03-06-027). Ecology Publication. Washington State Department of Transportation and Washington State Department of Ecology.

Richards, K. 1982. Rivers: Form and process in alluvial channels. Methuen & Co. New York NY. 358 p.

Robinson, D. A. Zundel, C. Kramer, R. Nelson, W. deRosset, J. Hunt, S. Hogan, and Y. Lai. 2019. Two-dimensional hydraulic modeling for highways in the river environment – Reference document. Federal Highway Administration Publication No. FHWA-HIF-19-061. October.

Schumm, S.A., M.D. Harvey and C.C. Watson. 1984. Incised channels: morphology, dynamics and control. Water Resources Publications, Littleton, Colorado.

StreamNet. 2020. Pacific Northwest salmonid and critical habitat distribution. StreamNet, Portland, Oregon. <http://www.streamnet.org/>. Accessed May 2020.

SWIFD (Statewide Washington Integrated Fish Distribution) online. 2020.
http://geo.wa.gov/datasets/4ed1382bad264555b018cc8c934f1c01_0. Accessed May 2020

USFS (United States Department of Agriculture, Forest Service). 2008. Stream Simulation: An Ecological Approach to Providing Passage for Aquatic Organisms at Road-Stream Crossings, Appendix E.

USACE (U.S. Army Corps of Engineers). 1994. Hydraulic design of flood control channels. EM-1110-2-1601.

USBR (United States Department of the Interior, Bureau of Reclamation). 2017. SRH-2D Version 3.2.4.

USDA NRCS (United States Department of Agriculture Natural Resources Conservation Service). 2012. Engineering Classification of Rock Materials.

USGS (United States Geological Survey) and Quantum Spatial. 2019. Olympic Peninsula, Washington 3DEP LiDAR- Area 1 Technical Data Report.

Washington Division of Geology and Earth Resources. 2016. Surface geology, 1:100,000--GIS data, November 2016: Washington Division of Geology and Earth Resources Digital Data Series DS-18, version 3.1, previously released June 2010
http://www.dnr.wa.gov/publications/ger_portal_surface_geology_100k.zip (accessed via the Washington State Department of Natural Resources (DNR) Geologic Information Portal, Aug 2021).

Washington Geological Survey. 2020a. Landslide protocol inventory mapping--GIS data, February, 2020: Washington Geological Survey Digital Data Series 19, version 2.0, previously released January, 2019.
https://fortress.wa.gov/dnr/geologydata/publications/data_download/ger_portal_landslide_inventory.z

ip (accessed via the Washington State Department of Natural Resources (DNR) Geologic Information Portal, Aug 2021).

Washington Geological Survey. 2020b. Landslide Compilation--GIS data, February 2020: Washington Geological Survey Digital Data Series 12, version 5.2, previously released January, 2019.

WDFW (Washington Department of Fish and Wildlife). 2005. Habitat Assessment Data for unnamed tributary (culvert 990730) at U.S. 101 MP 100.70. Unpublished.

WDFW. 2021. Washington State Fish Passage. Website accessed online:
<https://geodataservices.wdfw.wa.gov/hp/fishpassage/index.html>

WDFW. 2020a. SalmonScape. <http://wdfw.wa.gov/mapping/salmonscape>. Accessed May 2020.

WDFW. 2020b. Priority Habitats and Species map. Accessed May 2020.

WSDOT (Washington State Department of Transportation). 2019. *Hydraulics Manual*. Olympia, Washington. Publication M 23-03.06.

Washington State Department of Transportation (WSDOT). 2020. Geotechnical Report; US 101/SR 109- Remove Fish Barriers., September 29, 2020.

Wilcock, P.R. 1996. Estimating local bed shear stress from velocity observations. *Water Resources Research*, 32(11), pp.3361-3366.

Wilcock, P.R., A.F. Barta, C.C. Shea, G.M. Kondolf, W.G. Matthews, and J. Pitlick. 1996. Observations of flow and sediment entrainment on a large gravel-bed river. *Water Resources Research*, 32(9), pp.2897-2909.

Wydoski, R. and R Whitney. 2003. *Inland fishes of Washington*. University of Washington Press. Seattle, Washington. 220 pp.

Appendices

Appendix A: FEMA Floodplain Map

Appendix B: Hydraulic Field Report Form

Appendix C: SRH-2D Model Results

Appendix D: Streambed Material Sizing Calculations

Appendix E: Stream Plan Sheets, Profile, Details

Appendix F: Scour Calculations (to come in FHD)

Appendix G: Manning's Calculations

Appendix H: Large Woody Material Calculations

Appendix I: Future Projections for Climate-Adapted Culvert Design

Appendix J: Co-Manager Comments on Draft PHD Report and Stream Team Responses

Appendix A: FEMA Floodplain Map

NOTES TO USERS

is for use in administering the National Flood Insurance Program. It does not identify all areas subject to flooding, particularly from local drainage of small size. The community map repository should be consulted for updated or additional flood hazard information.

more detailed information in areas where **Base Flood Elevations (BFEs)** have been determined, users are encouraged to consult the Flood and Floodway Data and/or Summary of Stillwater Elevations tables contained in the Flood Insurance Study (FIS) Report that accompanies this FIRM. Users are aware that BFEs shown on the FIRM represent rounded whole-foot values. These BFEs are intended for flood insurance rating purposes only and are not to be used as the sole source of flood elevation information. Accordingly, elevation data presented in the FIS Report should be utilized in conjunction with the purpose of construction and/or floodplain management.

Base Flood Elevations shown on this map apply only to landward of 0.0' American Vertical Datum of 1988 (NAVD 88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study Report for this jurisdiction. Elevations in the Summary of Stillwater Elevations table should be used for construction and floodplain management purposes when they are higher than the elevations in this FIRM.

is of the **floodways** were computed at cross sections and interpolated cross sections. The floodways were based on hydraulic considerations with requirements of the National Flood Insurance Program. Floodway widths perpendicular to floodway data are provided in the Flood Insurance Study Report section.

was not in Special Flood Hazard Areas may be protected by **flood control** structures. Refer to Section 2.4 "Flood Protection Measures" of the Flood Insurance Study Report for information on flood control structures for this jurisdiction.

Section used in the preparation of this map was Universal Transverse Mercator (UTM) zone 10. The horizontal datum was NAD 83, GRS 1980. Differences in datum, spheroid, projection or UTM zones used in the FIRM for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

ations on this map are referenced to the North American Vertical Datum of 1988. Flood elevations must be compared to structure and ground elevations at the same vertical datum. For information regarding conversion of the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at nads.noaa.gov or contact the National Geodetic Survey at the following:

Information Services
NGS12
Geodetic Survey
#9202
1400 West Highway
Annapolis, Maryland 20710-3282
301-732-3242

current elevation, description, and/or location information for **bench marks** on this map, please contact the Information Services Branch of the National Survey at (301) 713-3242, or visit its website at <http://www.ngs.noaa.gov>.

Information shown on this FIRM was derived from multiple sources. The files were provided in digital format by Grays Harbor County GIS, WA DNR, and NGS. This information was compiled at various times during the time period 2004-2008.


Baseline depicted on this map represent the hydraulic modeling baselines for the flood profiles in the FIS report. As a result of improved topographic data, the baseline, in some cases, may deviate significantly from the channel or appear outside the SFHA.

Limits shown on this map are based on the best data available at the time. Because changes due to annexations or de-annexations may have occurred since this map was published, map users should contact appropriate officials to verify current corporate limit locations.

Refer to the separately printed **Map Index** for an overview map of the following layout of map panels; community map repository addresses; listing of Communities table containing National Flood Insurance Program data for each community as well as a listing of the panels on which each community is shown.

Information on available products associated with this FIRM visit the **Map Center (MSC)** website at <http://msc.fema.gov>. Available products may include: Letters of Map Change, a Flood Insurance Study Report, digital versions of this map. Many of these products can be ordered or downloaded directly from the MSC website.

For **questions about this map**, how to order products, or the National Flood Insurance Program in general, please call the **FEMA Map Information (FMIX)** at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA website at <http://www.fema.gov/business/info>.



LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAs) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD
The 1% annual chance flood (100-year flood), also known as the "base flood," is the flood that has a 1% chance of equalling or exceeding it in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, and VE. The Base Flood Elevation is the water elevation of the 1% annual chance flood.

ZONE A No Base Flood Elevations determined.
ZONE AE Base Flood Elevations determined.
ZONE AH Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevation determined.
ZONE AO Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
ZONE AR Special Flood Hazard Areas formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to protection from the 1% annual chance or greater flood.
ZONE A99 Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
ZONE V Coastal flood zone with velocity hazard (wave action); no Base Flood Elevation determined.
ZONE VE Coastal flood zone with velocity hazard (wave action); Base Flood Elevation determined.

FLOODWAY AREAS IN ZONE AE

The floodway is the channel of a stream plus any adjacent floodplain areas that must be encroached so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS

ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levees from 1% annual chance flood.

OTHER AREAS

ZONE D Areas determined to be outside the 0.2% annual chance floodplain.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

1% Annual Chance Floodplain Boundary

0.2% Annual Chance Floodplain Boundary

Floodway boundary

Zone D boundary

CBRS and OPA boundary

Boundary dividing Special Flood Hazard Area Zones and floodplains

Base Flood Elevation line and value; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Base Flood Elevation value where uniform within zone; elevation in feet

Appendix B: Hydraulic Field Report Form



Hydraulics Section

Hydraulics Field Report

Project Number:
10219302

Project Name:
UNT to WF Hoquiam R US 101 MP 98.47 (WDFW
993702)

Date:
5/14/2020

Project Office:
Tumwater Project Engineers Office

Time of Arrival:
9:00am

Location:
UNT to WF Hoquiam R US 101 MP 98.47

Time of Departure:
12:00pm

Purpose of Visit:
Site Reconnaissance

Weather:
Cloudy

Prepared By:
Rachel Ainslie

Meeting Location:
UNT to WF Hoquiam R, Grays Harbor County, US 101 MP 98.47

Attendance List:

Name	Organization	Role
Shaun Bevan	HDR	Senior Water Resources Engineer
Ian Welch	HDR	Biologist
Rachel Ainslie	HDR	Water Resources EIT

Bankfull Width:


Describe measurements, locations, known history, summarize on site discussion

HDR conducted an independent site visit on May 14, 2020 to measure bankfull width, collect pebble count data, and locate a reference reach. HDR walked the stream approximately 260 feet upstream and approximately 50 feet downstream of the existing 3' span circular concrete culvert crossing, measured along the stream centerline. HDR took three bankfull width measurements upstream of the crossing. See Figure 1 for measurement locations.

A secondary site visit with HDR, WSDOT, WDFW and the tribes has not yet been conducted to gain concurrence on bankfull widths and other design considerations due to COVID-19. Table 1 summarizes bankfull measurements taken during the May 14 site visit, which were used to determine the design bankfull width. The measured bankfull widths resulted in a **design average bankfull width of 7.4 feet**.

Table 1: Bankfull width measurements

BFW #	Width (ft)	Included in Design Average	Concurrence Notes
1	7.7	Yes	No BFW concurrence meeting has occurred
2	8.3	Yes	No BFW concurrence meeting has occurred
3	6.1	Yes	No BFW concurrence meeting has occurred
Design Average	7.4		No BFW concurrence meeting has occurred



Field Data Map
US 101 Unnamed Stream
To WF Hoquiam River

Mile Post 98.47
WDFW ID 993702

Reference Reach:

Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement

The reference reach is located approximately 150 feet upstream of the existing culvert inlet, shown in Figure 1 above. The reference reach is in a straight section of channel outside of backwater influence and primarily outside of the influence of LWM present in the reach. Cross section geometry in the reference reach will be used for design. All three bankfull widths were taken in the reference reach. A secondary site visit with HDR, WSDOT, WDFW, and the tribes has not yet been conducted to gain concurrence on reference reach appropriateness. Site conditions of the reference reach where the three bankfull width measurements were taken can be viewed in Figure 11.

Data Collection:

Describe who was involved, extents collection occurred within

HDR conducted an independent site visit on May 14, 2020. HDR walked the stream approximately 260 feet upstream and approximately 50 feet downstream of the existing culvert crossing. HDR took three bankfull width measurements and a pebble count upstream of the culvert crossing within the reference reach.

Observations:

Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.

Downstream Reach

At the far downstream extents of the survey, the Unnamed Tributary enters the West Fork Hoquiam at roughly a 90 degree angle. The West Fork Hoquiam is shallow prior to the confluence with the tributary, and transitions to a pool downstream of the confluence. The banks of the West Fork are approximately 3 feet tall and have large trees growing on them; additionally, the left bank upstream in the West Fork is formed by several logs. The streambed material appears to be primarily sands, gravels, and fines. Characteristics of the West Fork are shown in Figure 3.

The confluence between the West Fork Hoquiam and the Unnamed Tributary has a large rootwad log. The rootwad is located on the bank near the tributary and the log spans the West Fork Hoquiam (Figure 4). This is likely what causes the survey surface to appear irregular in this location. The rootwad diverts a small downstream branch of the tributary, resulting in two inflows to the West Fork – the larger tributary flow is displayed in the survey and is slightly north of the smaller branch. The smaller branch travels subsurface under the tributary bank to join the Hoquiam approximately five feet downstream of where the main tributary joins.

A debris jam is also located at the confluence with the West Fork. The banks of the tributary are approximately 1 foot tall near the confluence. Bank materials are soft and silty. The foliage is small growth such as shrubs, ferns, and grass. There is no active bank erosion. Some smaller trees roughly 3 inches in diameter are set back from the tributary by about 15 feet. The channel material is primarily silts and fines, with some gravel and sand present (Figure 5). Debris is frequent in the channel.

Upstream of the confluence by approximately 10 or 15 feet, there is a second debris jam (Figure 6). Some mud is packed in as well; it is racked up on two T-posts. At this upstream jam, the water surface drops approximately one or two feet.

At the culvert outlet, just upstream of the second debris jam, a large pool approximately 6 feet across has formed. The banks are approximately 2-3 feet tall near the culvert outlet. The streambed material is all fines. The material has also embedded itself into the culvert by a depth of approximately one foot. The concrete culvert was measured to be 36 inches in diameter. A photo of the culvert outlet is in Figure 7.

Upstream Reach

At the upstream inlet of the culvert, the culvert is raised off of the channel bed by 2-3 inches (Figure 8). There is a pool at the upstream end. At the pool inlet, debris is racked up (Figure 8). Banks are approximately 2 feet tall, vertical, and are incised near the culvert. The channel material is primarily fines with some gravels present. Banks are comprised of mud and silt with riparian vegetation of shrubs and ferns. Larger trees are set back from the channel by approximately 15 feet and their branches grow over the channel.

Approximately 25 feet upstream of the culvert inlet, a channel-spanning log weir causes a water drop of roughly 6 inches (Figure 9). The log weir marks a transition in channel characteristics for the tributary. Upstream of the log weir, the channel reach shifts to a more accessible floodplain. The left bank is low and sloped while the right bank is approximately 1 foot tall, with a low and flat floodplain. The banks are soft with organic litter and moss. The channel material is now primarily gravels with some fines, and there is more debris in the channel than previously. Riparian vegetation includes shrubs with some trees along the channel.

Roughly 30 feet upstream of the log weir, debris is racked in the channel. Shortly after, the channel travels through a bend of approximately 100 degrees. The banks become more vertical and are 3-4 feet in height. There are several live trees with roots in the banks. Just upstream of the bend, a tree several feet in diameter lies across the channel and has caused the channel to widen and scour. There are several more trees of larger diameters that have fallen across the channel in the 50 feet upstream of this point as well. Bank erosion was caused by the fallen trees.

Another log weir is located upstream of the LWM that caused channel scour and causes a drop in water surface of approximately 2 feet. The chosen reference reach is located upstream of this log weir, outside of backwater influence (Figure 11). Three bankfull widths were taken in this stretch of channel as well as a pebble count. The largest material found in the reference reach was 3.5 inches, but nearly all other material was smaller than 1 inch ($D_{95} = 0.8$ inches).

A second channel bend of approximately 110 degrees occurs 70 feet upstream of the first bend (Figure 12). The left bank at this point is completely vertical and 5-6 feet tall. The right bank is 1-2 feet tall with an accessible and flat floodplain. The channel material is almost completely fines around the bend.

Upstream of the bend by roughly 20 feet, a large rootwad log has fallen into the channel. The rootwad is in the channel and forces the tributary to flow under it.

Upstream of the rootwad, the banks are approximately 2 feet tall on either side with streambed material of primarily fines with some gravels. Debris is located in the channel. Shrubs and some trees grow along the banks. A log weir creates a water surface drop of approximately 6 inches. Upstream of the drop, the streambed material changes to primarily gravels with some fines; the weir has captured gravels upstream of it. This log weir is located approximately at the upstream survey extents.

Describe location of sediment sampling and pebble counts if available

One pebble count of about 150 pebbles was performed upstream of the culvert. The pebble count was taken in the reference reach, shown in Figure 1 above. The cumulative distribution and specific pebble sediment sizes are provided in Figure 2 and Table 2. Material primarily consisted of coarse sand in conjunction with fine to coarse gravels with only one observed cobble. Additional pebble counts were not conducted as it was apparent that the existing streambed material was smaller than WSDOT Standard Streambed Sediment.





Figure 2: Sediment size distribution



Table 2: Sediment properties upstream of project crossing

Particle	Upstream Diameter (in)
D ₁₆	0.1
D ₅₀	0.2
D ₈₄	0.4
D ₉₅	0.8
D ₁₀₀	3.5

Photos:

Any relevant photographs listed above

 WSDOT Hydraulics Section	Hydraulics Field Report		Project Number:																								
	Project Name: Coastal 29 Culverts		Date: 6/1/21																								
	Project Office: Kleinschmidt-R2		Time of Arrival:																								
	Stream Name: UNT to WF Hoquiam River		Time of Departure:																								
WDFW ID Number: 993702	Purpose of Site Visit Kickoff/First PHD Review/ID Data Needs		Prepared By: P DeVries																								
State Route/MP: 101/MP 98.47	Weather: Sunny																										
Meeting Location: At Site																											
Attendance List:																											
<table border="1"> <thead> <tr> <th>Name</th> <th>Organization</th> <th>Role</th> </tr> </thead> <tbody> <tr> <td>Paul DeVries</td> <td>Kleinschmidt-R2</td> <td>SDE</td> </tr> <tr> <td>Henry Hu</td> <td>Kiewit</td> <td>SDE</td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>				Name	Organization	Role	Paul DeVries	Kleinschmidt-R2	SDE	Henry Hu	Kiewit	SDE															
Name	Organization	Role																									
Paul DeVries	Kleinschmidt-R2	SDE																									
Henry Hu	Kiewit	SDE																									
Bankfull Width: <i>Describe measurements, locations, known history, summarize on site discussion</i>																											
Need to get more BFW measurements farther upstream, PHD XS' too close together; concur that downstream of culvert not a reference reach because of mainstem backwater																											
Reference Reach: <i>Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement</i>																											
Pebble count in PHD not representative of coarser deposits found in hydraulically sheltered locations																											
Data Collection: <i>Describe who was involved, extents collection occurred within</i>																											
Observations: <i>Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.</i>																											
Partial flow obstructions upstream composed of large logs dipping into channel; downstream primary roughness = vegetation in channel; backwatered from river at moderate flows; No fish seen; could be primarily juvenile Coho rearing habitat, appears usable																											
Pebble Counts/Sediment Sampling: <i>Describe location of sediment sampling and pebble counts if available</i>																											
Get sieve sample of coarser deposits to characterize coarser bedload material that is in short supply																											
Photos: <i>Any relevant photographs listed above</i>																											

 WSDOT Hydraulics Section	Hydraulics Field Report		Project Number:																								
	Project Name: Coastal 29 Culverts		Date: 6/16/21																								
	Project Office: Kleinschmidt-R2		Time of Arrival:																								
	Stream Name: UNT to WF Hoquiam River		Time of Departure:																								
WDFW ID Number: 993702	Purpose of Site Visit Additional PHD Data Collection		Prepared By: P DeVries																								
State Route/MP: 101/MP 98.47	Weather: Sunny																										
Meeting Location: At Site																											
Attendance List:																											
<table border="1"> <thead> <tr> <th>Name</th> <th>Organization</th> <th>Role</th> </tr> </thead> <tbody> <tr> <td>Paul DeVries</td> <td>Kleinschmidt-R2</td> <td>SDE</td> </tr> <tr> <td>Ben Cary</td> <td>Kleinschmidt-R2</td> <td>SDE</td> </tr> <tr> <td>Sebastian Ferraro</td> <td>Kleinschmidt-R2</td> <td>Modeler</td> </tr> <tr> <td>Henry Hu</td> <td>Kiewit</td> <td>Field Assistance</td> </tr> <tr> <td>Haley Koester</td> <td>Kiewit</td> <td>Field Assistance</td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>				Name	Organization	Role	Paul DeVries	Kleinschmidt-R2	SDE	Ben Cary	Kleinschmidt-R2	SDE	Sebastian Ferraro	Kleinschmidt-R2	Modeler	Henry Hu	Kiewit	Field Assistance	Haley Koester	Kiewit	Field Assistance						
Name	Organization	Role																									
Paul DeVries	Kleinschmidt-R2	SDE																									
Ben Cary	Kleinschmidt-R2	SDE																									
Sebastian Ferraro	Kleinschmidt-R2	Modeler																									
Henry Hu	Kiewit	Field Assistance																									
Haley Koester	Kiewit	Field Assistance																									
Bankfull Width: <i>Describe measurements, locations, known history, summarize on site discussion</i>																											
Performed two more BFW cross-section profile surveys farther upstream of reference reach (Photo 1 and 2) given that the PHD XS' were too close together; Values = 6.4' and 5.0', respectively.																											
Reference Reach: <i>Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement</i>																											
Reference reach can be extended upstream for gravel sampling and BFW determination; concur that reach downstream of existing culvert is not a reference reach because of mainstem flood backwater.																											
Data Collection: <i>Describe who was involved, extents collection occurred within</i>																											
		<p>Paul/Haley: mobile wood dimensions upstream, bulk gravel sample collection upstream.</p> <p>Ben/Sebastian/Henry: BFW cross-section surveys, map downstream wood obstructions (if any) close to culvert that could affect freeboard determination.</p>																									

Observations: *Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.*

- Mobile wood = small pieces; LWD that falls into channel too big to be mobilized, stays in place. Longest piece = 6.7', largest diameter = 5" (Table 1)

Table 1 – Mobile Wood Observations from June 2021 Site Visit

Date	Site ID		Piece 1		Piece 2		Piece 3		Piece 4		Notes
	WDFW	Kiewit	L (ft)	D (in)	L (ft)	D (in)	L (ft)	D (in)	L (ft)	D (in)	
6/16/2021	993702	23	5	2.5	6.7	1	5	3	4	5	

- No significant downstream channel obstruction seen that dominates over backwater effect from confluence with West Fork.

Pebble Counts/Sediment Sampling: *Describe location of sediment sampling and pebble counts if available*

Collected a sieve sample of a coarser gravel deposit on wetted channel bottom to characterize coarser bedload material that is in short supply, ~50 ft upstream of PHD reference reach (Photo 4); dry sieved, $D_{50}, D_{84} = 23 \text{ mm}, 47 \text{ mm}$ (Figure 1).




Figure 1 - Sediment Gradation Curve for June 2021 Sieve Sample

Photos: *Any relevant photographs listed above*

Photo 1: BFW Section #1



Photo 2: BFW Section #2



Photo 3: Upstream BFW survey location



Photo 4: Gravel sample collection location




 WSDOT Hydraulics Section	Hydraulics Field Report		Project Number:
	Project Name: Coastal 29 Culverts		Date: 7/13/21
	Project Office: Kleinschmidt-R2		Time of Arrival: 15:05
	Stream Name: UNT to WF Hoquiam River		Time of Departure: 15:45
WDFW ID Number: 993702	Purpose of Site Visit Additional PHD Data Collection		Prepared By: D. Sofield
State Route/MP: 101/MP 98.47	Weather: Extended dry period, Sunny		
Meeting Location: At Site			
Attendance List:			
Name		Organization	Role
Paul DeVries		Kleinschmidt-R2	SDE
Andrew Nelson		NHC	Geomorph/Review
Darrell Sofield		NHC	Geomorph/Review
Bankfull Width: <i>Describe measurements, locations, known history, summarize on site discussion</i>			
June observations were consistent with our field observations.			
Reference Reach: <i>Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement</i>			
NA			
Data Collection: <i>Describe who was involved, extents collection occurred within</i>			
NA			
Observations: <i>Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.</i>			
<ul style="list-style-type: none"> • <2 gal/min estimated flow, no salmonids observed. LWD is not mobile in the UNT. Sand and gravel were mobile. • Channel upstream of the culvert transitioned morphology as the gradient decreases. <ul style="list-style-type: none"> ○ Directly upstream of the culvert, the channel consists of riffle pool morphology. BFW 2-5 ft, BFH 1.5-2 ft (Photo 1). ○ 50 ft upstream, the channel widens to 4-6 feet, 0.5 to 1 deep, and the channel bed consists of courser gravel (<45-64mm) ○ 100 ft upstream channel goes to a wood-faced step-pool (Photo 2). • Downstream of the culvert outlet, UNT is incising into a hardpan till (silt with sand and rounded gravel (Photo 3), and a gradient significantly increases. • UNT flows into a 4 ft deep pool on the WF Hoquiam River (Photo 4), No grade controls were present in the UNT, and therefore the profile adjustment is potentially controlled by the river. • On the WF Hoquiam River 1st downstream hydraulic controls were a series of buried channel spanning logs with a combined head loss of 1.25 feet over 40 feet (Photo 5). • Downstream of the river changes to a riffle pool channel, with LWD in the channel. LD trees exist within a mature riparian zone. (Photo 6) 			
Field Interpretation: Need to account for X channel adjustment, maybe 1.25 ft additional incision + jam scale aggregation, check elevation with the survey.			
Pebble Counts/Sediment Sampling: <i>Describe location of sediment sampling and pebble counts if available</i>			
NA			
Photos: <i>Any relevant photographs listed above</i>			

Photo 1: Pool Riffle Morph and BFW Section #1, US of the culvert



Photo 2: Wood Faced step-pool, ~200 ft upstream of the culvert.



Photo 3: Downstream of the culvert, the channel is incising into silt.



Photo 4: WFH River looking downstream at a deep pool at the confluence of UNT (left of photo)



Photo 5: Looking downstream at two Wood-controlled steps on the WFH River, downstream of the confluence with the UNT.




Photo 6: Gravel on pool riffle of WFH River, downstream of the confluence with the UNT.




Appendix C: SRH-2D Model Results

Appendix C: SRH-2D Model Results

Existing Profile Tributary




Cross Section
STA 52+38 (F)
Existing Conditions




2-Year Tributary 100-Year Tributary 500_year Tributary Existing Ground

Cross Section
STA 52+07 (E)
Existing Conditions




2-Year Tributary 100-Year Tributary 500_year Tributary Existing Ground

Cross Section
STA 51+64 (D)
Existing Conditions




2-Year Tributary 100-Year Tributary 500_year Tributary Existing Ground

Cross Section
STA 51+08 (C)
Existing Conditions




2-Year Tributary 100-Year Tributary 500_year Tributary Existing Ground

Cross Section
STA 50+19 (A)
Existing Conditions




2-Year Tributary 100-Year Tributary 500_year Tributary Existing Ground

Existing Profile Coincident Peaks




Cross Section
STA 52+38 (F)
Existing Conditions




— 2-Year Coincident Peaks — 100-Year Coincident Peaks — 500-year Coincident Peaks — Existing Ground

Cross Section
STA 52+07 (E)
Existing Conditions




— 2-Year Coincident Peaks — 100-Year Coincident Peaks — 500-year Coincident Peaks — Existing Ground

Cross Section
STA 51+64 (D)
Existing Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-year Coincident Peaks Existing Ground

Cross Section
STA 51+08 (C)
Existing Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-year Coincident Peaks Existing Ground

Cross Section
STA 50+19 (A)
Existing Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-year Coincident Peaks Existing Ground

Natural Profile Tributary




Cross Section
STA 2+15 (F)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Cross Section
STA 1+85 (E)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Cross Section
STA 1+42 (D)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Cross Section
STA 1+00 (C)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Cross Section
STA 0+61 (B)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Cross Section
STA 0+18 (A)
Natural Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Natural Ground

Natural Conditions WSEL




— Existing Ground - - - Cross Sections — 500-Year Coincident Peaks
— 100-Year Coincident Peaks — 2-Year Coincident Peaks — 2080 100-Year Coincident

Upstream Cross Section
STA 2+15 (F)
Natural Conditions




— Ground — 500-Year Coincident Peaks — 100-Year Coincident Peaks
— 2-Year Coincident Peaks — 2080 100-Year Coincident

Upstream Cross Section
STA 1+85 (E)
Natural Conditions




Upstream Cross Section
STA 1+42 (D)
Natural Conditions




Ground 500-Year Coincident Peaks 100-Year Coincident Peaks
2-Year Coincident Peaks 2080 100-Year Coincident

Upstream Cross Section
STA 1+00(C)
Natural Conditions




— Ground — 500-Year Coincident Peaks — 100-Year Coincident Peaks
— 2-Year Coincident Peaks — 2080 100-Year Coincident


Crossing Cross Section
STA 0+61 (B)
Natural Conditions




DownstreamCross Section
STA 0+18 (A)
Natural Conditions



Proposed Profile Tributary




Cross Section
STA 0+18 (A)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground

Cross Section
STA 0+61 (B)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground Structure

Cross Section
STA 1+00 (C)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground

Cross Section
STA 1+42 (D)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground

Cross Section
STA 1+85 (E)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground

Cross Section
STA 2+15 (F)
Proposed Conditions




2-Year Tributary 100-Year Tributary 500-Year Tributary 2080 100-Year Tributary Proposed Ground

Proposed Profile Coincident Peaks




— 2-Year — 100-year — 500-Year — Proposed Ground — 2080 100-Year - - - - Cross Sections

Cross Section
STA 0+18 (A)
Proposed Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-Year Coincident Peaks 2080 100-Year Coincident Peaks Proposed Ground

Cross Section
STA 0+61 (B)
Proposed Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-Year Coincident Peaks 2080 100-Year Coincident Peaks Proposed Ground Structure

Cross Section
STA 1+00 (C)
Proposed Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-Year Coincident Peaks 2080 100-Year Coincident Peaks Proposed Ground

Cross Section
STA 1+42 (D)
Proposed Conditions




2-Year Coincident Peaks 100-Year Coincident Peaks 500-Year Coincident Peaks 2080 100-Year Coincident Peaks Proposed Ground

Cross Section
STA 1+85 (E)
Proposed Conditions




— 2-Year Coincident Peaks — 100-Year Coincident Peaks — 500-Year Coincident Peaks — 2080 100-Year Coincident Peaks — Proposed Ground

Cross Section
STA 2+15 (F)
Proposed Conditions



2-Year Coincident Peaks 100-Year Coincident Peaks 500-Year Coincident Peaks 2080 100-Year Coincident Peaks Proposed Ground


Existing Condition, Tributary Only, 2-Year Peak Year Flow, Water Surface Elevation



Existing Condition, Tributary, 2-Year Peak Year Flow, Water Depth




Existing Condition, Tributary, 2-Year Peak Year Flow, Velocity




Existing Condition, Tributary, 2-Year Peak Year Flow, Shear Stress




Existing Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Surface Elevation




Existing Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Depth




Existing Condition, Coincident Peaks, 2-Year Peak Year Flow, Velocity




Existing Condition, Coincident Peaks, 2-Year Peak Year Flow, Shear Stress




Existing Condition, Tributary, 100-Year Peak Year Flow, Water Surface Elevation




Existing Condition, Tributary, 100-Year Peak Year Flow, Water Depth



Existing Condition, Tributary, 100-Year Peak Year Flow, Velocity




Existing Condition, Tributary, 100-Year Peak Year Flow, Shear Stress




Existing Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Surface Elevation




Existing Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Depth




Existing Condition, Coincident Peaks, 100-Year Peak Year Flow, Velocity




Existing Condition, Coincident Peaks, 100-Year Peak Year Flow, Shear Stress




Existing Condition, Tributary, 500-Year Peak Year Flow, Water Surface Elevation




Existing Condition, Tributary, 500-Year Peak Year Flow, Water Depth



Existing Condition, Tributary, 500-Year Peak Year Flow, Velocity




Existing Condition, Tributary, 500-Year Peak Year Flow, Shear Stress




Existing Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Surface Elevation




Existing Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Depth




Existing Condition, Coincident Peaks, 500-Year Peak Year Flow, Velocity



Existing Condition, Coincident Peaks, 500-Year Peak Year Flow, Shear Stress



Natural Condition, Tributary, 2-Year Peak Year Flow, Water Surface Elevation



Natural Condition, Tributary, 2-Year Peak Year Flow, Water Depth




Natural Condition, Tributary, 2-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Tributary, 2-Year Peak Year Flow, Shear Stress




Natural Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Depth



Natural Condition, Coincident Peaks, 2-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Coincident Peaks, 2-Year Peak Year Flow, Shear Stress




Natural Condition, Tributary, 100-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Tributary, 100-Year Peak Year Flow, Water Depth




Natural Condition, Tributary, 100-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Tributary, 100-Year Peak Year Flow, Shear Stress




Natural Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Depth




Natural Condition, Coincident Peaks, 100-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Coincident Peaks, 100-Year Peak Year Flow, Shear Stress



Natural Condition, Tributary, 500-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Tributary, 500-Year Peak Year Flow, Water Depth




Natural Condition, Tributary, 500-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Tributary, 500-Year Peak Year Flow, Shear Stress




Natural Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Depth



Natural Condition, Coincident Peaks, 500-Year Peak Year Flow, Velocity Magnitude



Natural Condition, Coincident Peaks, 500-Year Peak Year Flow, Shear Stress




Natural Condition, Tributary, 2080 100-Year Peak Year Flow, Water Surface Elevation



Natural Condition, Tributary, 2080 100-Year Peak Year Flow, Water Depth




Natural Condition, Tributary, 2080 100-Year Peak Year Flow, Velocity Magnitude




Natural Condition, Tributary, 2080 100-Year Peak Year Flow, Shear Stress




Natural Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Water Surface Elevation




Natural Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Water Depth




Natural Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Velocity Magnitude



Natural Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Shear Stress



Proposed Condition, Tributary, 2-Year Peak Year Flow, Water Surface Elevation



Proposed Condition, Tributary, 2-Year Peak Year Flow, Water Depth



Proposed Condition, Tributary, 2-Year Peak Year Flow, Velocity Magnitude




Proposed Condition, Tributary, 2-Year Peak Year Flow, Shear Stress




Proposed Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Surface Elevation




Proposed Condition, Coincident Peaks, 2-Year Peak Year Flow, Water Depth




Proposed Condition, Coincident Peaks, 2-Year Peak Year Flow, Velocity Magnitude



Proposed Condition, Coincident Peaks, 2-Year Peak Year Flow, Shear Stress




Proposed Condition, Tributary, 100-Year Peak Year Flow, Water Surface Elevation




Proposed Condition, Tributary, 100-Year Peak Year Flow, Water Depth



Proposed Condition, Tributary, 100-Year Peak Year Flow, Velocity Magnitude




Proposed Condition, Tributary, 100-Year Peak Year Flow, Shear Stress




Proposed Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Surface Elevation




Proposed Condition, Coincident Peaks, 100-Year Peak Year Flow, Water Depth




Proposed Condition, Coincident Peaks, 100-Year Peak Year Flow, Velocity Magnitude



Proposed Condition, Coincident Peaks, 100-Year Peak Year Flow, Shear Stress




Proposed Condition, Tributary, 500-Year Peak Year Flow, Water Surface Elevation



Proposed Condition, Tributary, 500-Year Peak Year Flow, Water Depth




Proposed Condition, Tributary, 500-Year Peak Year Flow, Velocity Magnitude




Proposed Condition, Tributary, 500-Year Peak Year Flow, Shear Stress




Proposed Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Surface Elevation




Proposed Condition, Coincident Peaks, 500-Year Peak Year Flow, Water Depth




Proposed Condition, Coincident Peaks, 500-Year Peak Year Flow, Velocity Magnitude



Proposed Condition, Coincident Peaks, 500-Year Peak Year Flow, Shear Stress




Proposed Condition, Tributary, 2080 100-Year Peak Year Flow, Water Surface Elevation




Proposed Condition, Tributary, 2080 100-Year Peak Year Flow, Water Depth



Proposed Condition, Tributary, 2080 100-Year Peak Year Flow, Velocity Magnitude



Proposed Condition, Tributary, 2080 100-Year Peak Year Flow, Shear Stress




Proposed Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Water Surface


Elevation




Proposed Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Water Depth



Proposed Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Velocity Magnitude



Proposed Condition, Coincident Peaks, 2080 100-Year Peak Year Flow, Shear Stress



Appendix D: Streambed Material Sizing Calculations

Summary - Stream Simulation Bed Material Design

Project: Coastal 29 Site 23 UNT to West Fork Hoquiam River
By: Paul DeVries

Observed Gradation:				
Location:	Pebble Count 1			
	D ₁₀₀	D ₈₄	D ₅₀	D ₁₆
ft	0.29	0.16	0.08	0.01
in	3.50	1.90	1.00	0.10
mm	89	48	25.4	2.5

Observed Gradation:				
Location:				
	D ₁₀₀	D ₈₄	D ₅₀	D ₁₆
ft	0.00	0.00	0.00	0.00
in				
mm	0	0	0.0	0.0

Design Gradation:				
Location:	Design Mix			
	D ₁₀₀	D ₈₄	D ₅₀	D ₁₆
ft	0.29	0.17	0.07	0.01
in	3.50	2.02	0.81	0.10
mm	89	51	20.6	2.5

Observed Gradation:				
Location:				
	D ₁₀₀	D ₈₄	D ₅₀	D ₁₆
ft	0.00	0.00	0.00	0.00
in				
mm	0	0	0.0	0.0

Determining Aggregate Proportions

Per WSDOT Standard Specifications 9-03.11

Rock Size		Streambed	Streambed Cobbles					Streambed Boulders			D _{size}
[in]	[mm]	Sediment	4"	6"	8"	10"	12"	12"-18"	18"-28"	28"-36"	
36.0	914								100	100.0	
32.0	813								50	100.0	
28.0	711								100	100.0	
23.0	584								50	100.0	
18.0	457							100		100.0	
15.0	381							50		100.0	
12.0	305					100				100.0	
10.0	254					80				100.0	
8.0	203				100	80	75			100.0	
6.0	152			100	80	67	62			100.0	
5.0	127			80	68	53	40			100.0	
4.0	102		100	71	57	40	35			100.0	
3.0	76.2		80	63	45	34	30			96.0	
2.5	63.5	100	65	54	37	28	25			93.0	
2.0	50.8	92	50	45	29	23	20			83.6	
1.5	38.1	79	35	32	21	17	15			69.8	
1.0	25.4	65	20	18	13	11	10			56.0	
0.75	19.1	58	8	5	5	5	5			48.0	
No. 4 =	4.75	30								24.0	
No. 40 =	0.425	10								8.0	
No. 200 =	0.0750	5								4.0	
% per category		80	20	0	0	0	0	0			--> 100%
% Cobble & Sediment		80.0	20.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	100.0%

Streambed Mobility/Stability Analysis

Modified Shields Approach

References:

Stream Simulation: An Ecological Approach to Providing Passage for Aquatic Organisms at Road-Stream Crossings

Appendix E--Methods for Streambed Mobility/Stability Analysis

Limitations:

D₈₄ must be between 0.40 in and 10 in

uniform bed material (D₁ < 20-30 times D₅₀)

Slopes less than 5%

Sand/gravel streams with high relative submergence


Y _s	165	specific weight of sediment particle (lb/ft ³)
Y	62.4	specific weight of water (lb/ft ³)
τ _{D50}	0.045	dimensionless Shields parameter for D ₅₀ , use table E.1 of USFS manual or assume 0.045 for poorly sorted channel bed

Flow 2-YR 100-Yr 100-YR Climate Change

Average Modeled Shear Stress (lb/ft ²)		0.1	0.6	0.7
τ _{ci}		0.0	5.3	9.3
0.97	No Motion	No Motion	No Motion	No Motion
0.94	No Motion	No Motion	No Motion	No Motion
0.90	No Motion	No Motion	No Motion	No Motion
0.85	No Motion	No Motion	No Motion	No Motion
0.79	No Motion	No Motion	No Motion	No Motion
0.75	No Motion	No Motion	No Motion	No Motion
0.70	No Motion	No Motion	No Motion	No Motion
0.66	No Motion	No Motion	No Motion	No Motion
0.62	No Motion	No Motion	No Motion	Motion
0.57	No Motion	No Motion	No Motion	Motion
0.54	No Motion	Motion	Motion	Motion
0.50	No Motion	Motion	Motion	Motion
0.46	No Motion	Motion	Motion	Motion
0.44	No Motion	Motion	Motion	Motion
0.41	No Motion	Motion	Motion	Motion
0.38	No Motion	Motion	Motion	Motion
0.33	No Motion	Motion	Motion	Motion
0.31	No Motion	Motion	Motion	Motion
		mm	inches	feet
	D16	2.6	0.1	0.01
	D50	20.6	0.8	0.07
	D84	51.3	2.0	0.17

Sediment Gradation

Streambed Mix



Appendix E: Stream Plan Sheets, Profile, Details

SEC. 23 T.19N. R.10W. W.M.

LEGEND

EXISTING STREAM ALIGNMENT

EXISTING INDEX CONTOUR

EXISTING INTERMEDIATE CONTOUR

STREAM SCALABLE EDGE


EXISTING EDGE OF PAVEMENT

EXISTING TREE

EXISTING GUARDRAIL

56

---250---



PRELIMINARY - NOT FOR CONSTRUCTION

SITE 23

FILE NAME				c:\users\rick_doherty\appdata\local\bentley\project\working\dlr\klewit-us-pw.bentley.com_klewit-us-pw-01\0149532\20C511_23_993702_PS_CE_Stream\exst_01.dgn			
TIME				7:18:12 PM			
DATE				10/28/2021			
PLOTTED BY				Rick Doherty			
DESIGNED BY				B. CARY			
ENTERED BY				R. DOHERTY			
CHECKED BY				P. DEVRIES			
PROJ. ENGR.				K. KOKENGE			
REGIONAL ADM.				J. WYNANDS			
REVISION				DATE BY			

REGION NO.
10

STATE
WASH

JOB NUMBER
20C511

CONTRACT NO.

FED.AID PROJ.NO.

LOCATION NO.

993702



P.E. STAMP BOX

DATE



US 101/SR 109
GRAYS HARBOR/JEFFERSON/CLALLAM
REMOVE FISH BARRIERS PROJECT

STREAM EXISTING CONDITIONS

PLAN REF NO

CR1










SHEET


OF

XX
SHEETS

SEC. 23 T.19N. R.10W. W.M.

LEGEND

NEW STREAM ALIGNMENT	
EXISTING INDEX CONTOUR	
EXISTING INTERMEDIATE CONTOUR	
STREAM SCALABLE EDGE	
EXISTING EDGE OF PAVEMENT	
EXISTING TREE	
EXISTING GUARDRAIL	
CUT LINE	
FILL LINE	




NOTES:

1. SLOPES SHOWN OUTSIDE HYDRAULIC OPENING ARE FOR ILLUSTRATIVE PURPOSES ONLY TO DEPICT ESTIMATED AREA OF POTENTIAL IMPACT. FINAL AREAS OF IMPACT TO BE DETERMINED PENDING GEOLOGICAL AND STRUCTURAL INVESTIGATION, STRUCTURE TYPE, AND STRUCTURE LOCATION.
2. PROPOSED STRUCTURE SHOWN FOR ILLUSTRATIVE PURPOSES ONLY. STRUCTURE TYPE, SIZE, AND LOCATION TO BE DETERMINED DURING LATER PHASE OF DESIGN. PROPOSED STRUCTURE SHALL NOT ENCROACH INTO HYDRAULIC OPENING SHOWN ON PLAN.
3. LIDAR DATA WAS USED IN LOCATIONS WHERE DAYLIGHT LIMITS EXTEND BEYOND DETAILED SURVEY.

PRELIMINARY - NOT FOR CONSTRUCTION

[illegible]




PRELIMINARY - NOT FOR CONSTRUCTION

SITE 23

FILE NAME	c:\users\rick_doherty\appdata\local\bentley\project\working\dlr\kiewit-us-pw.bentley.com_klewit-us-pw-01\0149532\20C511_23_993702_PS_PR_CP_StreamProf_01.dgn
TIME	11:39:20 AM
DATE	11/19/2021
PLOTTED BY	Rick Doherty
DESIGNED BY	B. CARY
ENTERED BY	R. DOHERTY
CHECKED BY	P. DEVRIES
PROJ. ENGR.	P. DEVRIES
REGIONAL ADM.	J. WYNANDS
REVISION	DATE BY

REGION NO.	STATE	FED.AID PROJ.NO.
10	WASH	
JOB NUMBER	20C511	
CONTRACT NO.		LOCATION NO.
		993702



US 101/SR 109
GRAYS HARBOR/JEFFERSON/CLALLAM
REMOVE FISH BARRIERS PROJECT
STREAM PROPOSED CONDITIONS

PLAN REF. NO.
CR3
SHEET
1
OF
1
SHEETS



(SEE NOTES 5 AND 6)



NOTES:

1. SEE SPECIAL PROVISIONS "AGGREGATE FOR STREAMS, RIVERS, AND WATERBODIES" FOR STREAMBED MATERIAL. MATERIAL DEPTH IS APPROXIMATE. FINAL DEPTH TO BE DETERMINED FOLLOWING SCOUR ANALYSIS.
2. SLOPES SHOWN OUTSIDE HYDRAULIC OPENING ARE FOR ILLUSTRATIVE PURPOSES ONLY TO DEPICT ESTIMATED AREA OF POTENTIAL IMPACT. FINAL AREAS OF IMPACT TO BE DETERMINED PENDING GEOLOGICAL AND STRUCTURAL INVESTIGATION, STRUCTURE TYPE, AND STRUCTURE LOCATION.
3. PROPOSED STRUCTURE SHOWN FOR ILLUSTRATIVE PURPOSES ONLY. STRUCTURE TYPE, SIZE, AND LOCATION TO BE DETERMINED DURING LATER PHASE OF DESIGN. PROPOSED STRUCTURE SHALL NOT ENCROACH INTO MINIMUM OPENING ON PLAN.
4. SEE SHEET CR3 FOR MINIMUM LOW CHORD ELEVATION THROUGHOUT STRUCTURE.
5. FROM UT 0+15.68 TO UT 0+25.68 TRANSITION FROM EXISTING TO SECTION A.
6. FROM UT 1+40.00 TO UT 1+60.00 TRANSITION FROM SECTION A TO EXISTING.

PRELIMINARY - NOT FOR CONSTRUCTION

SITE 23

US 101/SR 109

**GRAYS HARBOR/JEFFERSON/CLALLAM
REMOVE FISH BARRIERS PROJECT**

STREAM SECTIONS

AN REF NO

R4

SHEET
1
OF
1
SHEETS

[illegible]

SEC. 23 T.19N. R.10W. W.M.

LEGEND

NEW STREAM ALIGNMENT

EXISTING INDEX CONTOUR

EXISTING INTERMEDIATE CONTOUR

STREAM SCALABLE EDGE

EXISTING EDGE OF PAVEMENT

EXISTING TREE

EXISTING GUARDRAIL

CUT LINE

FILL LINE

LOOSE LOG WITH ROOTWAD AND BRANCHES


EMBEDDED LOG WITH ROOTWAD

5

250

CUT

FILL



PRELIMINARY - NOT FOR CONSTRUCTION

SITE 23

FILE NAME				\$\$\$\$\$DESIGNFILENAME\$\$\$\$\$			
TIME				\$TIMES			
DATE				\$\$\$\$DATE\$\$\$			
PLOTTED BY				\$\$USERNAME\$			
DESIGNED BY				B. CARY			
ENTERED BY				R. DOHERTY			
CHECKED BY				P. DEVRIES			
PROJ. ENGR.				P. DEVRIES			
REGIONAL ADM.				J. WYNANDS			
REVISION				DATE BY			

REGION NO.
10

STATE
WASH


JOB NUMBER
20C511

CONTRACT NO.

FED.AID PROJ.NO.

LOCATION NO.

993702



Washington State Department of Transportation



US 101/SR 109
GRAYS HARBOR/JEFFERSON/CLALLAM
REMOVE FISH BARRIERS PROJECT

STREAM LARGE WOODY MATERIAL CONCEPT

PLAN REF NO
CR5

SHEET
OF
1
SHEETS

Appendix F: Scour Calculations

Appendix G: Manning's Calculations



Job No. 2900.001

Calc. No.

Design By PDV

Date 07/22/21

Project Olympic 29

Check By BC

Date 07/22/21

Subject Mannings n - Cowan Method in Arcement & Schneider (1989)

SR Route: US 101 **Mile Post:** 98.47 **Stream Crossing ID:** 993702

	Channel						
Person	nb	n1	n2	n3	n4	m	n
PDV	0.030	0.020	0.015	0.002	0.020	1.000	0.087
BC	0.030	0.010	0.009	0.015	0.015	1.020	0.081
						Selected	0.084

	Floodplain/Riparian						
Person	nb	n1	n2	n3	n4	m	n
PDV	0.035	0.005	0.000	0.002	0.050	1.000	0.092
BC	0.035	0.008	0.000	0.020	0.055	1.000	0.118
						Selected	0.105

Appendix H: Large Woody Material Calculations

WSDOT Large Woody Material for stream restoration metrics calculator										
State Route# & MP		US101 MP 98.47		Key piece volume		1.310 yd ³				
Stream name		UNT WF Hoquiam R		Key piece/ft		0.0335 per ft stream				
length of regrade ^a		145 ft		Total wood vol./ft		0.3948 yd ³ /ft stream		Taper coeff. -0.01554		
Bankfull width		9 ft		Total LWM ^c pieces/ft stream		0.1159 per ft stream		LF _{rw} 1.5		
Habitat zone ^b		Western WA						H _{dbh} 4.5		
Log type	Diameter at midpoint (ft)	Length(ft) ^d	Volume (yd ³ /log) ^d	Rootwad?	Qualifies as key piece?	No. LWM pieces	Total wood volume (yd ³)	DBH based on mid point diameter (ft)	D _{root collar} (ft)	L/2-Lrw (ft)
A	1.25	30	1.36	yes	yes	5	6.82	1.38	1.45	13.125
B	1.50	25	1.64	yes	yes	3	4.91	1.59	1.66	10.25
C	1.00	30	0.87	yes	no	9	7.85	1.14	1.21	13.5
D			0.00				0.00		0.00	0
E			0.00				0.00		0.00	0
F			0.00				0.00		0.00	0
G			0.00				0.00		0.00	0
H			0.00				0.00		0.00	0
I			0.00				0.00		0.00	0
J			0.00				0.00		0.00	0
K			0.00				0.00		0.00	0
L			0.00				0.00		0.00	0
M			0.00				0.00		0.00	0
N			0.00				0.00		0.00	0
O			0.00				0.00		0.00	0
P			0.00				0.00		0.00	0
			No. of key pieces	Total No. of LWM pieces	Total LWM volume (yd ³)					
Design			8	17	19.6					
Targets			5	17	57.2					
			surplus	on target	deficit					
^a includes length through crossing, regardless of structure type										
^b choose one of the following Forest Regions in the drop-down menu (if in doubt ask HQ Biology). See also the Forest Region tab for additional information										
Western Washington low (generally <4,200 ft. in elevation west of the Cascade Crest)										
Alpine (generally > 4,200 ft. in elevation and down to ~3,700 ft. in elevation east of the Cascade crest)										
Douglas fir-Ponderosa pi (mainly east slope Cascades below 3,700 ft. elevation)										
^c LWM (Large Woody Material), also known as LWD (Large Woody Debris) is defined as a piece of wood at least 10 cm (4") diam. X 2 m (6ft) long (Fox 2001).										
^d includes rootwad if present										

Appendix I: Future Projections for Climate-Adapted Culvert Design

Future Projections for Climate-Adapted Culvert Design

Project Name: 993702

Stream Name: UNT to WF Hoquiam River

Drainage Area: 106 ac

Projected mean percent change in bankfull flow:

2040s: 16.1%

2080s: 21.6%

Projected mean percent change in bankfull width:

2040s: 7.8%

2080s: 10.3%


Projected mean percent change in 100-year flood:

2040s: 1.9%


2080s: 9%



Projected percent change in bankfull width



Projected percent change in 100-year flow



Black dots are projections from 10 separate models

The Washington Department of Fish and Wildlife makes no guarantee concerning the data's content, accuracy, precision, or completeness. WDFW makes no warranty of fitness for a particular purpose and assumes no liability for the data represented here.

Appendix J: Co-Manager Comments on Draft PHD Report and Stream Team Responses

1.0 Executive Summary

This report lists comments received from the Co-Managers (Tribes and Washington Department of Fish and Wildlife (WDFW)) on the initial Preliminary Hydraulic Design (PHD) Reports prepared by WSDOT for the site Bundle 1, Site 23 (#993702), and present Stream Team's responses.

There were selected comments that are pertinent to multiple sites that will be resolved through the design process, and can be summarized and addressed generally as follows:

General Comment	General Response
1. The design should consider the potential for transport of large wood pieces to the road crossing from upstream, and ensure that the pieces can be passed downstream underneath the structure through a sufficiently wide opening, and with appropriate freeboard.	Most of the channels in this bundle are relatively small, where fallen trees have typically remained in place, and only small diameter, short debris pieces appear to be transported downstream via the channel or over the floodplain. The initial draft PHD report did not evaluate this feature per se. In subsequent field work performed mid-June 2021, the Stream Team evaluated the role of wood in the channel more closely, by estimating the largest diameter and length of wood pieces that appear to be mobile and could create a blockage underneath the structure that would be likely to adversely affect flood conveyance, structural integrity, and fish passage.
2. Where velocity ratios calculated in the draft PHDs are >1.1, the design of a longer structure should be considered to account for climate change, or more detailed analyses are needed to support the present proposed span length.	Velocity ratio, which is a metric effectively representing effects of flow contraction by structures on streams with a relatively wide floodplain, will be reviewed as part of a more focused modeling evaluation and design of channel cross-section profile under the structure. Calculated velocity ratios are changing substantially from the initial PHD report values as the design considers stability of the bank side slopes of the constructed channel. The initial PHD report specifies a typical side slope of 2H:1V for the stream simulation design, but this profile is highly unlikely to remain in place after one or more high flows because of the (i) expected absence of bank stabilizing vegetation underneath the replacement structure, and (ii) increased instability of stones on a slope angle that is not substantially lower than the angle of repose when velocities increase during a flood event. Accordingly, the cross-section profile design was redesigned to have side slopes gentler than 2H:1V under the replacement structure. In addition, the hydraulically smoother substrate within a replacement culvert will result in calculating increased velocity ratios exceeding typical criteria used for bridge structures no matter what. These phenomena were considered during development of the channel design and are documented in the design report with appropriate details.
3. WDFW requested more detail on how natural conditions topography was developed in the vicinity of the road crossing for the hydraulic modeling in section 4.3 of the PHDs.	All cross-sections used to generate topography in the vicinity of the road crossing are presented in an appendix. The new Stream Team does not have all information documenting the decisions made in developing the terrain, but note that the cross-sections and topography represent a scoping level approximation of what natural conditions might have looked like. The design will be generally constrained to be somewhere between existing and assumed natural conditions, thus we

	propose focusing effort primarily on the proposed design in subsequent updating of the PHD report.
4. WDFW prefers to (i) utilize wood within the proposed crossing, following wood density criteria for undisturbed channels as reported by Fox and Bolton, (ii) compare current conditions against the criteria, and (iii) evaluate LWD and channel complexity design and layout prior to FHD completion.	WDFW and QIN will have the opportunity to review and comment on LWM and channel complexity design before the FHD is completed. The Stream Team will evaluate the role of wood in the channel more closely, including the effects of (i) downstream channel blockages/obstructions that increase backwater upstream through the culvert, and (ii) increased roughness on conveyance and bedload transport through the reconstructed reach. LWD layout at the PHD level is conceptual and may change to reflect site specific conditions. A detailed design will be developed as part of the FHD that is tailored to the site. In general, WSDOT does not propose to install LWM within the replacement structure footprint because of the effect of the above features on structure function, stability, and maintenance.
5. There are differences in bankfull width determinations at some sites across stakeholders.	Where there are apparent differences, or where the Stream Team still had questions after an initial site visit on June 1, 2021, additional cross-section profiles were surveyed in the field in mid-June 2021 for bankfull width measurements. The relevant resulting measurements are summarized in specific responses below. Supporting data are presented in the Final PHD report.

2.0 Introduction

Specific comments and responses are provided below for culvert Bundle 1, Site 23 (#993702). Different formats were used in processing the Tribe and WDFW's comments. QIN comments are presented first, followed by WDFW comments, for each site. For some (but not all) sites, WSDOT had provided an initial response in 2020, and the response has since been updated by the Stream Team in this document; WSDOT's initial responses are replicated here for the administrative record and are represented as italics plus strikeout fonts delimited between brackets [].

3.0 Comments and Responses – Bundle 1, Site 23 (#993702)

WDFW NUMBER:		PROJECT NAME	DATE OF REVIEW
993702		UNT to WF Hoquiam - US 101 MP 98.47	
CONTACT PHONE:		PROJECT CONTACT:	COMMENT DUE DATE
		Nick Harvey - Harveni@wsdot.wa.gov	
REVIEWER PHONE:		REVIEWERS NAME:	REVIEWERS ORGANIZATION:
360-591-4580		Caprice Fasano	Quinault Indian Nation
COMMENT #	PAGE/SHEET	REVIEWERS COMMENT	DESIGNERS COMMENTS
1		BFW measurements in reference reach one, were spaced very close together and may not have captured the prevailing conditions.	[HQ Hydraulics is supportive of using the 9ft average and increasing size to 13ft.] Stream Design Engineer/Fluvial Geomorphologist surveyed two more bankfull cross-section profiles upstream of the reference reach on 6/16/21, away from the influence of the culvert and where a bankfull morphology was evident.

Appendix J – Comments and Responses

Bundle 1, Site 23 (#993702)

2		PHD bankfull width does not match the expected value based on independent site visit conducted by QIN. See details in comment #3.	<i>[HQ Hydraulics is supportive of using the 9ft average and increasing size to 13ft.]</i> See response to comment 3.
3		DOT # 1 – nonconcur – QIN measured 9 ft DOT #2 – nonconcur – QIN measured 10 ft DOT #3 - near influence of wood and should be removed from average	<i>[HQ Hydraulics is supportive of using the 9ft average and increasing size to 13ft.]</i> The estimated BFWs based on cross-section profile morphology were 6.4' and 5.0', compared with 8.3', 7.7' and 6.1' measured with tapes previously downstream. Averaging the two new measurements with the QIN values results in a calculated BFW = 7.6', slightly larger than the value in the initial PHD report.
4		QIN measured an average of 9 ft for BFW. We recommend increasing structure to 13 ft. vs proposed 11 ft.	<i>[HQ Hydraulics is supportive of using the 9ft average and increasing size to 13ft.]</i> Although the new measurements are smaller, WSDOT HQ Hydraulics is supportive of using the 9 ft BFW average and increasing replacement structure opening size to 13 ft wide.
5		Due to increase in BFW recommend increasing freeboard to 2 ft.	<i>[2ft will be recommended at this time; will need to determine what impacts that has as the design progresses.]</i> Stream Team concurs with increasing freeboard criterion to 2 ft per WDFW guidelines for increased BFW.
6		Due to limited staff and review time available, QIN plans on reviewing channel geometry, substrate, LWD, and stormwater BMP's at a later date. Please keep us updated during future phases of the design.	<i>[noted]</i> Noted.
7		How much channel loss will occur with new alignment? Recommend providing mitigation loss of channel.	<i>[Approx. 23 ft. We will need to discuss possible mitigation further.]</i> Approx. 23 ft. WSDOT will need to discuss possible mitigation further.

WDFW Review Comments on WSDOT Preliminary Hydraulic Design Report	WDFW Site ID: <u>993702</u> Stream Name: <u>Unnamed</u> Tributary to WF Hoquiam River US/SR <u>101</u> MP <u>98.47</u>	Comments By: <u>Dave Collins / Pad</u> <u>Smith</u> Date: <u>February 18,</u> <u>2021</u>	<u>Limit Comments limited to does not meet:</u> <ul style="list-style-type: none"> • <u>2013 Water Crossing Design Guidelines,</u> <u>Or</u> • <u>Stream Design Checklist</u> <u>Or</u> • <u>Relevant WAC</u>
--	--	---	--

Appendix J – Comments and Responses
Bundle 1, Site 23 (#993702)

No.	PHD Page	Topic	Comment with Citations from 2013 WCDG, Stream Design Checklist, or WAC	Stream Team Response
		General Comment	General traffic control plans need to be included and reviewed with these projects. Often these result in some of the biggest impacts to the existing habitat on these types of projects.	Traffic Control Plans will be provided separately from Hydraulic Design Reports
1	9	2.6 Wildlife connectivity	Was a habitat connectivity analysis ever requested or completed?	A Wildlife Connectivity memo from WSDOT's Environmental Services Office was not required for this site.
2	9-16	Section 2.7	The presentation of stream features is done well in this section. WDFW would like you to include BF information within this section where appropriate. Please include wood and complexity components as observed in the field when designing the stream channel components.	Noted; BF information is provided in section 2.8, not necessary to also include in Section 2.7?
3	17-24	Section 2.8	In general, for most of these projects that have been developed during the Covid 19 pandemic, there have not been the typical multi agency site visits to discuss reference reach selection and BF width measurements. Independent site visits were conducted for this site and WDFW measured BF widths of 6-11 ft. Table 3 indicates a WSDOT average of 7.4 ft and is inconsistent with our measurements. This variation should be discussed at a future meeting in order to resolve.	See responses to QIN comments 1, 3, and 4. All measurements were performed upstream of Hwy 101 because channel morphology downstream is controlled by backwater from mainstem river and deposition.
4	22	Fig 21	Profile indicates some potential for regrade near the crossing and that there is a rather significant grade break right at the 101 crossing site. This will need to be assessed in greater detail as the design progresses.	Potential for aggradation and regrade potential has been assessed in final PHD, in section 2.8.4.
5	30	Boundary conditions	Was the model developed with normal depth boundary conditions at the Hoquiam River as indicated on pg.30 or the time series data shown on pg. 31? In either case this could affect model results at the 101 crossing. Additional discussion is needed on the modeling approach which is probably best handled via an in person short meeting. Make sure we are capturing the WF Hoquiam River backwater curves within the model domain and if the curves were utilized that should cover the concern.	Downstream boundary conditions were reviewed by the Stream Team and updated to develop a rating curve for the WF Hoquiam River.
6	41	Table 8	Can the values in the table for the structure be populated from the HY-8 output?	Not easily with HY8, and with the existing culvert flowing full, most of the values in the table would not be relevant, especially since the structure will be removed.
7	41	4.3 Natural conditions	Please show x-section used to create natural condition mesh and describe how it represents a natural condition. This item will likely require additional discussion.	See general response 3 above.

Appendix J – Comments and Responses
Bundle 1, Site 23 (#993702)

8	47	4.4 Channel Design	The rationale used to eliminate x- sections to determine the FUR needs to be discussed in more detail. Eliminating station 0+18 removes the only effective X-section downstream from this evaluation.	A review by Stream Design Engineer indicates that (i) the justification given in the PHD that flooding at the subject cross-section reflects the mainstem river and not the project stream hydrology and hydraulics is reasonable, and (ii) if the mainstem hydraulic effect were ignored, it is likely that a calculate FUR for that cross-section would not change the design given the calculated velocity ratios for the site overall.
9	49	4.4 Channel Design	The low flow channel through the crossing and constructed reaches will be reviewed when completed.	Noted
10	56	Table 13	Velocities within the banks through the structure are significantly higher than that on the banks outside of the structure. This item will need further discussion.	The implications of this comment are not clear. This comment will need to be revisited after considering the new proposed cross-section profile in the replacement structure and the velocity ratio paradox identified in general response 2 above.
11	57	Section 4.7	Structure type and length are still undetermined at this time. This information will be reviewed once it is available.	Noted
12	61	5.2 Channel Complexity	Is it feasible to utilize wood within the proposed crossing at this site? Please compare the wood density from the Fox and Boulton model to that observed during site reconnaissance. LWD design and layout has not yet been established and will need to be evaluated along with any proposed meander bars when completed.	See general response 4 above.
13	66	8 Scour Analysis	Design elements such as scour protection, lateral migration and aggregation/degradation are typically deferred until later in the design process and WDFW will participate in reviewing those concepts when they are available. For this project, please address how the existing drops from natural wood will be accounted for. These issues could have the potential to require modifications to the structure size selected based on the results of the analysis.	Noted

In addition to your comments above, please respond to the following questions even if the response may duplicate comments previously entered in the table.

Appendix J – Comments and Responses

Bundle 1, Site 23 (#993702)

1. Based on the information available and on previous discussions, does the design of the project, considering it is at this draft level of completeness, follow the guidelines included in WDFW's Water Crossing Design Guidelines? If "no", reference the number of the comment(s) in the response table above that address instances where WDFW guidelines are considered not followed. **The design is currently evolving but the intent appears to meet WCDG's**
2. Based on the information available and on previous discussions, do you foresee problems with this project receiving an HPA? If "yes", reference the number of the comment(s) in the response table above that address instances where these requirements are considered not followed. **If the comments above are addressed, we do not foresee issuance of an HPA being a problem**
3. Does the PHD bankfull width match the expected value based on site visits, prior measurements, or derived from other described methods? If "no", list the expected bankfull width to be used for design or reference comment number in the table above that discusses expected bankfull width. **For the most part, yes, see comments above.**
4. Does the minimum span of the replacement structure match or exceed the minimum value expected by the reviewer? If "no", reference the number of the comment(s) in the response table above that address structure span being different than expected. **For the most part, yes, see comments above.**